

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T. N. S. R. E. W.		
2. PROPERTY CONTROLLING IN SECTION	5 T. 19 N. R. 12 W.	3; 9; 10; 16	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 9, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A - ~~Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

16
Drove 3/4"x21" pipe
7" B. Oak N20°W 57.3
5" W. Oak N60°E 82.3
Ctr. bit. rd. Due S 3.2
Set cedar post w/loc. tag
Due N 33'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 3 Established NW corner, S½ NW¼ of Sec. 5 at single proportion distance to 1838 G.L.O. survey.
- 9 Established 1/8 corner per standard B.L.M. instructions.
- 10 Established 1/8 corner per standard B.L.M. instructions.
- 16 Established 1/8 corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5	9	10
Set 5/8"x43" rerod w/RLS cap & cedar post w/loc. tag	Set 5/8"x34" rerod & cedar post w/loc. tag	Drove 3/4"x18" pipe in center N-S gravel road
6" B. Oak N60°W 53.1	8" B. Oak N45°W 19.5	Power Pole N55°W 59.37
4" B. Oak N35°E 21.4	5" B. Oak S85°E 10.0	Power Pole N45°E 31.26
Ctr. N-S dirt road	Ctr. Trail Due E 102'	2" W. Pine S50°E 42.70
Due W 19'		Set cedar post w/loc. tag
		N45°W 47'

SIGNED BY: Carl F. Roser DATE: 7-9-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: _____ DATE: _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY: _____ DATE: _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY