

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF --: | LOCATED IN --: | CORNER CODE NUMBER |
|--------------------------------------|-------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 19 N. R. 12 W. | H-1; I-3 |
| 2. PROPERTY CONTROLLING IN SECTION | T. 19 N. R. 12 W. | 7; 16 |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. S. R. E. W. | |
| 4. LOT NO., RECORDED PLAT | | |
| 5. PRIVATE CLAIMS | | |

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 17, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

16
Drove 3/4"x20" pipe
3" R. Pine N50°W 82.9
13" W. Oak S10°E 37.3
Ctr. bit.rd. Due N 3.5'
Set cedar post w/loc. tag
Due N 66'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-1 Established N $\frac{1}{4}$ corner of Sec. 3 equidistant between the NE & NW corners of Sec. 3 and on line between the SE & SW corners of Sec. 34, T20N-R12W.
- I-3 Fd. and accepted 1/2" rod per RLS Clint Cole. Corner is in line with center of bit-surfaced roads to N & S.
- 7 Reestablished N 1/8 corner on E line of Sec. 3, on line between 1/4 corner to S & sec. corner to N & at prorated distance to G.L.O. survey, which equals J. W. Nichoson method of establishing 1/8 corner in August 1907.
- 16 Established 1/8 corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | |
|-------------------------------------|-------------------------|--------------------------------|
| H-1 | I-3 | 7 |
| Set DNR Mon. & Cedar Post | Found 1/2" Iron Rod | Drove 5/8"x34" rerod w/RLS cap |
| 12" Cedar N50°E 60.8 | Power Pole N60°W 103.05 | 4" Maple N80°W 37.5 |
| 6" B. Ash S20°E 33.8 | Power Pole N20°E 123.89 | 8" Ash S40°E 52.2 |
| S $\frac{1}{4}$ Sec. 34 (T20N-R12W) | 12" B. Oak S25°E 99.15 | Set ced.post w/loc. tag |
| S89°54'W 50.42 | Ctr. E-W bit. road | Due W 33' |
| | Due N 6' | Ctr. N-S bit.rd. Due E 3' |
| | | Ctr. Creek Due S 253' |

SIGNED BY Carl F. Roser 7-9-80 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET