

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 19 N. R. 12 W.	G-3; G-4; G-5; H-5
2. PROPERTY CONTROLLING IN SECTION--	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION--	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 9, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C. (continued)

H-5
Set DNR Mon. cap on 1"x68" pipe & cedar post w/loc. tag
9" B. Oak S15°E 132.5
13" Maple N85°W 211.5
Ctr. gravel rd. Due S 157'
Fd. old ced. post S54°30'W 17.8'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-3 Fd. 1" bolt, pieces of crockery & brick (buried) per old Co. Surv. Geo. H. Johnson.
- G-4 Fd. & accepted 3/4" pipe that fits both G. H. Johnson's witnesses.
- G-5 Fd. & accepted RR rail (buried vertical) & one G. H. Johnson wit. Center of road to north is west 17'±.
- H-5 Reestablished 1/4 corner equidistant & on line between section corners to E & W. Corner falls in 8" of water in cattail marsh.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3	G-4	G-5
Fd. 1" bolt & raised with 3/4" x24" pipe	Fd. 3/4" pipe w/bracket	Fd. RR rail in ctr. E-W gravel road
5" W. Pine N30°W 59.8	3" W. Pine N65°W 45.6	9" W. Oak N30°E 46.5
4" W. Pine N20°E 78.8	4" W. Pine S45°W 50.0	8" Maple S50°E 39.0
Ctr. rd. S Due E 27'	3" W. Pine S75°W 38.1	6" Maple S40°W 41.7
Set cedar post w/loc. tag Due N 33'	Set ced. post w/loc. tag Due E 33'	Set cedar post w/loc. tag Due S 33'
Ctr. E-W bit. rd. Due S 3'	Ctr. N-S dirt rd. Due E 5'±	
	Ctr. trail W'yly Due N 2'±	

SIGNED BY Carl F. Roser 7-9-80 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY