

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 N. R. 12 W.	F-2; G-2
2. PROPERTY CONTROLLING IN SECTION 4	T. 19 N. R. 12 W.	5; 9
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 5, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A- Description of original monument and accessories and of subsequent restoration
 C. (continued)

- 9
- Set 5/8"x34" rerod w/RLS cap
- & cedar post w/loc. tag
- 3" B. Oak N60°W 17.7
- NE leg steel tower #3872
- S10°E 165.6
- Ctr. power line S89°W 84'
- Ctr. of trail S89°W 133'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-2 Established center of Sec. 4 at intersection of one-quarter lines.
- G-2 Reestablished 1/4 corner single proportion to 1838 G.L.O. survey.
- 5 Established NE corner of SE-NW, Sec. 4, on line 6 at prorated distance to 1838 G.L.O. survey, between center & N 1/4 corner of Sec. 4.
- 9 Established E 1/8 on E-W 1/4 line, Sec. 4, per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--|--|---|
| <p>F-2</p> <p>Set 5/8"x34" rerod w/RLS cap in old pine stp. & ced. post w/loc. tag</p> <p>3" B. Oak N05°W 3.2</p> <p>4" B. Oak S40°W 18.8</p> <p>4" W. Pine S30°E 63.4</p> | <p>G-2</p> <p>Set DNR Mon. & Cedar Post</p> <p>4" B. Oak N85°W 28.1</p> <p>6" & 8" R. Maple N30°E 29.5</p> <p>4" W. Oak S35°E 7.2</p> <p>N-S Rand. Due W 0.1</p> | <p>5</p> <p>Set 5/8"x34" rerod w/RLS cap & cedar post w/loc. tag</p> <p>5" W. Pine N50°W 65.0</p> <p>9" Maple N60°E 15.4</p> <p>SW leg steel tower #3868 N25°E 211.0</p> <p>Ctr. power line S89°E 227'</p> <p>Ctr. trail rd. S89°E 172'</p> |
|--|--|---|

SIGNED BY Carl F. Roser 7-9-80 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO.

SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY