

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. N. S., R. E. W.	
2. PROPERTY CONTROLLING IN SECTION 4	T. 19 N. R. 12 W.	7; 14; 15; 16
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S., R. E. W.	
4. LOT NO....., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 9, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on, 19....., found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A - Description of original monument and accessories and/or subsequent restorations

C. (continued)

16
Drove 3/4"x27" pipe (flush)
8" W. Oak N20°E 48.6
4" W. Pine N60°E 97.4
Set cedar post w/loc. tag
Due N 33'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 7 Established N 1/8 corner on E line Sec. 4, single proportion to 1838 G.L.O. survey.
- 14 Established 1/8 corner per standard B.L.M. instructions.
- 15 Established 1/8 corner per standard B.L.M. instructions.
- 16 Established 1/8 corner per standard B.L.M. instructions. Corner falls in center of E-W blacktop road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

7	14	15
Set 5/8"x40" rerod w/RLS cap & cedar post w/loc. tag	Set 5/8"x40" rerod w/RLS cap & cedar post w/loc. tag	Drove 3/4"x27" pipe (flush)
6" Cedar N30°W 18.1	9" B. Oak S75°E 15.0	3" R. Pine N25°W 58.1
6" Ash S60°E 19.0	7" B. Oak S40°W 3.8	8" W. Oak N45°E 53.4
5" Cedar S05°E 14.4	Ctr. power line	Ctr. E-W bit.rd.DueN 1'
N-S random line	Due S 539'	Set cedar post w/loc. tag
Due W 0.15		Due N 33'


SIGNED BY: Carl F. Roser 7-9-80 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY: _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY