

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
LAKE

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>12W</u>	<u>A-1</u>
	T _____ R _____	<u>A-2</u>
	T _____ R _____	<u>B-1</u>
	T _____ R _____	
2. Property Controlling in Section	S <u>6</u> T _____ R _____	<u>2</u>
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, C. F. ROSER, in a field survey on 8-20, 19 85, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-1	A-2	B-1	2
FD & ACCEPTED JACK OVER 1/2" x 24" PIPE FOR NW COR S-6 (COR COMM. TO FOUR TWP'S); FITS ONE G. BLASS WIT (1948). SWP TIES; W EDGE 400'±W, E EDGE 328'±E, N EDGE 160'±N, S EDGE 162'±S.	FD & ACCEPTED 1/2" x 18" REROD BY RLS CLINT COLE, FOR 1/4 COR COMM TO SEC 6 (T19N-R12W) & SEC 1 (T19N-R13W). COLE REESTAB. COR PROPORTIONATE NEA TO GLO (RUN OUT SEC; GLO HAD 80.00 CH ON LINE COMM TO SEC'S 1 & 6). COR FALLS IN SPRUCE & TAMARACK SWP (BOGGY); N EDGE IS 730'±N & S EEDGE IS 490'±S.	RESTORED 1/4 COR S-6 (T19-R12W) ON LINE BET. FD SE COR & S1/4 COR OF S-31 (T20N-R12W) & AT PRORATED DISTANCE TO 1838 GLO DISTANCE ( RUN OUT SECTION) BETWEEN FD NE COR & NW COR OF S-6. CTR TWO TRACK (WINDING RD) SOUTH IS W, 8'±. CTR E-W SAND RD (IN CURVE) IS 15'±N.	DROVE 5/8" x 34" REROD FOR E 1/8 COR ON N LINE OF S-6. THE E 1/8 COR ON THE S LINE OF S-31 (T20N-R12W) IS N89°50'W, 36.70.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1	A-2	B-1	2
FD CAR JACK OVER 1/2" x 24" PIPE, REPLACED W/DNR MON ON 1" x 6" PIPE & CED POST.	FD 1/2" x 18" REROD W/RLS CAP #17615 & ADDED DNR MON ON 1" x 5" PIPE & CEDAR POST.	DROVE 5/8" x 34" REROD (BURIED 0.4') W/RLS CAP.	DROVE 5/8" x 34" REROD W/RLS CAP.
24" W PINE 605°W 169.05 5" TAMARACK N45°E 59.30 8" TAMARACK N83°W 157.10 COR FALLS IN SPRUCE SWAMP	*3" SPRUCE N47°W 16.80 *7" SPRUCE S58°W 11.43 *6" SPRUCE S50°E 26.12 5" TAMARACK N85°E 14.12	4" W OAK 535°E 31.07 10" B OAK S10°E 22.73 10" W OAK S65°W 28.10 S1/4 S-31, T20N-R12W N89°50'W 37.18 SET CEDAR POST W/LOC TAG SOUTH 33'	7" OAK S15°W 74.44 14" OAK S60°W 55.20 SET CEDAR POST W/LOC TAG SOUTH 33' COR FALLS IN APPROX CTR E-W SAND Rd.

\* = C. Cole Wits.

Signed by Carl F. Roser 02-02-88 Date \_\_\_\_\_

Surveyor's Michigan License No. 12028

