

SURVEY & REMONUMENTATION

JAN 14 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
 For corners in

Lake _____
 (County)

	Located In:		Corner Code #
	19N	12W	
1. Public Land Survey	T _____	R _____	D-5
	T _____	R _____	
	T _____	R _____	
	T _____	R _____	
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

RECORDED
 LAKE COUNTY, MI.
 LIBER 004 PAGE 0087

DEC 12 11 37 AM '97

Lucinda H. Dechant
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert L. Wetherell in a field survey on October 13, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-5 - 1/4 Corner Common to Sections 8 & 17, T19N, R12W, Lake Co., MI.
- | | |
|---|-------------------------------------|
| <u>1838 - S. Sibley, G.L.O.</u> | <u>1972 - George Blass, LS 5489</u> |
| #1 - 10" Pine N31°E 22 Links | L.C.R.C. - Liber 02, Pg. 10 |
| #2 - 16" Pine S17°W 14 Links | Found old 4" x 4" Concrete Monument |
| <u>Undated - George Johnson, Co. Sur.</u> | #4 - 12" B. Oak S10°W 27.85' |
| #3 - 6" B. Oak N64°E 62 Links | #5 - 12" B. Oak N55°W 25.32' |
| | #6 - 12" J. Pine N57°E 70.14' |

- 1993 - Carl Roser, LS 12028
 L.C.R.C. - Liber 03, Pg. 176
 Found Broken Concrete Monument
 Replaced with D.N.R. Monument
 (Pipe and Aluminum Disc.)
 #6 - 14" J. Pine S55°E 70.05'
 #7 - 9" W. Pine N40°W 35.1'
 #8 - 5" W. Pine S10°W 26.3'
 #9 - 5" W. Pine S55°W 15.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 - 1/4 Corner Common to Sections 8 & 17, T19N, R12W, Lake Co., MI.

I found the D.N.R. Capped Pipe Monument.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Found Stump, #5 Found Stump, #6 Found in good condition, #7 Found in good condition, #8 Found in good condition, #9 Found in good condition.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
 IN ACCORDANCE WITH P.A. 345
 CHAIRMAN R.L.W.
 DATE 12-10-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 - 1/4 Corner Common to Sections 8 & 17, T19N, R12W, Lake Co., MI.

I accepted the D.N.R. Capped Pipe Monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 12" W. Pine N33°W 35.70' (60d spike in N.E. side) #7
- 7" W. Pine S18°W 26.39' (60d spike in W. side) #8
- 7" W. Pine S62°W 16.05' (60d spike in N.W. side) #9
- 5" Tw. W. Oak N28°W 15.35' (60d spike in E. side)

Signed by Robert L. Wetherell

Date 12-12-97

Surveyor's Michigan License No. 24624

