

SUPPLEMENT  
REMONUMENTATION

MAY 16 1997

COMPLETION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0363

For corners in  
Lake

(County)	Located In:	Corner Code #
1. Public Land Survey	T 19N R 12W	J-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS  
*Shirley M. DeWard*

SEP 12 3 10 PM '96

RECORDED  
LAKE COUNTY, MI.

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on August 23, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1 - North 1/4 corner of Section 2, T19N, R12W - South Newkirk Township, Lake County, Mi.

Not set by original survey and no history of previous establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 - North 1/4 corner of Section 2, T19N, R12W - South Newkirk Township, Lake County, Mi.

I set the corner on the Township line in line with old fence and tree line to the South. This position fits a proportional split between respective Section corners by 16 feet. Corner is 6 feet more or less South of East and West dirt road.

Distance to the Northeast corner of Section 2 - 2632.67 feet  
Distance to the Northwest corner of Section 2 - 2666.10 feet

WATIFIED BY THE LAKE CO. PEER REVIEW GROUP  
IN ACCORDANCE WITH P.A. 345  
CHAIRMAN B. J. W.  
DATE 8-27-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 - North 1/4 corner of Section 2, T19N, R12W - South Newkirk Township, Lake County, Mi.

I set a 3/4" x 24" re-bar with a Lake County Brass Cap and is accepted as the best available evidence of the position of the corner.

- 10" Maple N36°W 35.52' (60d spike in S.W. side)
- 12" Tw. Maple N10°E 36.81' (60d spike in W. side)
- 12" B. Oak S68°E 74.67' (60d spike in S. side)
- 14" Maple S64°W 32.66' (60d spike in N.W. side)
- 3/4" Iron with Lake County Brass Cap - Due West 65.73' (South 1/4 corner Sectin 35, T20N, R12W)

Signed by Robert L. Wetherell  
24624  
Surveyor's Michigan License No. \_\_\_\_\_

September 6, 1996

Date \_\_\_\_\_

