

**SURVEY &
REMONUMENTATION**

JAN 25 2001 LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

SECTION

For corners in Lake _____	Located in:	Corner Code#
1. Public Land Survey	T 19 N R 12 W	K-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____ Recorded Plat _____		
5. Private Claims _____		

RECORDED
LAKE COUNTY, MI.
LIBER 004 PAGE 0256
May 5 10 27 AM '00
Shelley Myers
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Robert L. Wetherell, in a field survey on March 2, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

K-2 - 1/4 Corner common to Sections 1 & 2, T19N, R12W

A. Description of original monument and accessories and/or subsequent restoration:

1838 - S. Sibley, G.L.O.

#1 - 16' Sugar S55°E 10 Links
#2 - 10' Sugar S53°W 13 Links

1929 - G. H. Johnson, Co. Surveyor

Did not call for a corner but showed the following distances.
#3 - Measured 2600' South
#4 - Measured 2836' North

B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:


I found an old cast iron leg from a wood stove in the center of a North and South road and in line with fences East and West.
Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Measured 2609', #4 Measured 2822' North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 3/4" x 24" rebar with a Lake County Remon Cap directly over the cast iron stove leg, and is accepted as a careful and faithful reestablishment of the position of the original corner.

15" Tw. Elm S87°E 35.99' (60d spike in S. side)
N.E. corner Garage Foundation S20°W 122.25'
N.W. corner Garage Foundation N51°E 59.62'
11" R. Pine N17°E 143.1' (center of tree)

WITNESSED BY THE LAKE COUNTY PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN R.L.W.
DATE 4-11-2000



Signed by Robert L. Wetherell
Surveyor's Michigan License No. 24624

Date April 12, 2000