

MAY 1 8 1997

COMM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Lake _____ (County)	Located In:	Corner Code =#
1. Public Land Survey	T 19N R 12W	L-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED
 LAKE COUNTY, MI.
 SEP 12 3 10 PM '96
 REGISTER OF DEEDS
Debbie H. Peterson

LIBER 003 PAGE 0365

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Wetherell, in a field survey on August 19, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1 - North 1/4 corner Section 1, T19N, R12W, South Newkirk Twp., Lake Co., Mi.

Not set by G.L.O. and no history of previous establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 - North 1/4 corner Section 1, T19N, R12W, South Newkirk Twp., Lake Co., Mi.

I set the corner on the Township Line equal distances between Northeast corner Section 1 and Northwest corner Section 1. Corner falls 2 feet more or less South of an East and West gravel road and in line with the extension of old fence to South.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
 IN ACCORDANCE WITH P.A. 345
 CHAIRMAN G.L.W.
 DATE 8-27-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 - North 1/4 corner Section 1, T19N, R12W, South Newkirk Twp., Lake Co., Mi.

I set a 3/4" x 24" re-bar with Lake County Brass Cap, and is accepted as the best available evidence of the position of the corner.

- 12" Cedar S37°E 83.89' (60d spike in E. side)
- 7" Elm S20°E 40.45' (60d spike in W. side)
- 6" Elm S75°W 61.25' (60d spike in S. side)
- 3/4" iron with Lake County Brass Cap - West 31.20' (South 1/4 corner Section 36, T20N, R12W)

Signed by Robert L. Wetherell Date September 5, 1996
 Surveyor's Michigan License No. 24624

