

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Lake _____ (County)	Located In	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>12W</u> T <u>19N</u> R <u>13W</u>	<u>A7</u> <u>M7</u>
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 2, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7	●												●
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| <p><u>A7 & M7</u> - GLO - Set post - S. Sibley - 1838
Pine 8" N20°W 48 L.; Pine 8" S18°W 28 L.</p> <p>- GLO - T19N, R12W - S. Sibley - 1838
corrected between 18 & 19
Pine 8" S26°E 28L. Pine 8" N18°E 15L.</p> <p>- L. S. Cobb - 1878
P. Pine 10" S86°30'W 119.5L
P. Pine 10" N25°30' W 191.5' L.</p> <p>- G. West - 1908 - find stake - BT's burned out. B. Oak
6" N25°W 88.5 L; B. Oak 7" N22°E 106 L.</p> | <p>- G. H. Johnson - CSR L.1, pg. 32-1912 - piece of iron, Oak stake
B. Oak stake : B. Oak N87°E 70 ½ L.
P. Pine 12" S1°W 207 L.</p> <p>- F Jones - 1930's - J. Pine 10" S61°W 59'
B. Oak 13" N22°E 69'</p> <p>-G. Blass - Fd. "T" iron fence post 30" long.
Blaze in 8" J. Pine N18°E 52.18'
Blaze in 8" J. Pine N66°30' W 30.15'
Blaze in 10" J. Pine S50°30'W 38.37'
Blaze in 10" J. Pine S31°E 26.80'</p> |
|---|---|

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

A7 & M7 - Standard corner common to Sec. 13 & 24, T19N, R13W and Sec. 18 & 19, T19N, R12W - Fd. 'T' iron fence post 28" long at ground level as noted by Blass. Fd. B Oak snag with Blaze at N25°W 58.4' per West. Fd. remains of B. Oak with Blaze per West & Jones at N22°E 69'. Fd. remains of B. Oak stp. at N87°E 47' per Johnson. Fd. Blass BT stps. in agreement w/ 'T' fence post. 'T' iron fence post accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 & M-7 - Replaced 'T' iron fence post w/ 4" DNR Alum. cap on 1" X 36" Galv. iron pipe.
Set Blue Carsonite post 1' N, Set Steel Fence post 1' E
N28°W 12.43' to set N&T in NE side 9" J. Pine scribed 'XBT'
N41°E 29.40' to set N&T in NW side 10" J. Pine scribed 'XBT'
S34°W 19.41' to set N&T in W side 7" J. Pine scribed 'XBT'
S20°E 16.97' to set N&T in W side 4" J. Pine
N76°W 22.54' to set N&T in W side 6" J. Pine scribed 'XBT'



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 11/26/2001