

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Lake _____ (County)	Located In	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>12W</u>	<u>A8</u>
	T <u>19N</u> R <u>13W</u>	<u>M8</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 16, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

<p><u>A8 & M8</u> - GLO - Set ¼ post - S. Sibley - 1838 Pine 8" N73°W 46 L. Pine 8" N54°W 10L. - L. S. Cobb - 1878 - tin pail & dragtooth for stake. P. pine 10" S86°30'w 1.195 ch. P. Pine 10" N25°30'W 1.915 ch.</p>	<p>- G. West - 1908 - finds drag tooth in pail (old notes) J. Pine 6" N 45°W 90 ½ L. J. Pine 7" S 41½°E 92 ½ L.</p>
--	---

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

A8 & M8 - Standard ¼ corner common to Sec. 19, T19N, R12W and Sec. 24, T19N, R13W - Fd. 1"x1" sq. X 11" long iron dragtooth in rusted remains of tin pail per Cobb and West. Found moss mound at West's SE BT site. All other BT's gone. Also found ½ " rebar N 67°50' E 6.89' of Cobb's position. Have no record on ½ " rebar (could be by P. Salisbury) so I reject it. CL of N-S 2 track is 14' West. Cobb indicates he had original stake so accepted dragtooth in tin pail as a careful & faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 & M-8 - Replaced dragtooth & tin pail w/ 4" DNR Alum. cap on 1" X 36" Galv. iron pipe in a ring of stones. Placed dragtooth inverted on E. side & tin pail remains all at base of monument as memorials. Set Blue Carsonite post 1' NE. Set Steel Fence post 1' S.
 N22°W 5.60' to set N&T in W side 14" J. Pine scribed 'XBT'
 N85°E 32.59' to set N&T in N side 5" J. Pine scribed 'XBT'
 S45°W 10.26' to set N&T in NE side 6" J. Pine scribed 'XBT'
 N78°W 56.38' to set N&T in W side 9" B. Oak scribed 'XBT'
 N67°50'E 6.89' to Fd. ½ " rebar



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/26/2001