

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Lake Located In Corner Code #
 (County)

1. Public Land Survey	T	<u>19N</u>	R	<u>12W</u>	<u>A9</u>
	T	<u>19N</u>	R	<u>13W</u>	<u>M9</u>
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 15, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9	●												●
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p><u>A9 & M9</u> - GLO - Set post - S. Sibley - 1838
 Pine 6" N21°W 84 L.
 Pine 6" S14°W 68 L.</p> <ul style="list-style-type: none"> - GLO - T19N, R12W Sub. - S. Sibley - 1838
 Corrected E. from corner. - Old Co. sur. notes (L. S. Cobb - 1878?)
 Thunder Mug filled / bottles & glass for corner. - F. Jones Bk. - 1930's - 1878- A thunder mug filled with bottles for corner. Witnesses gone -1908. | <ul style="list-style-type: none"> - LCRC - L. 2, P. 107 - C.F. Roser - 1973
 Recovered 2 - Fn. Post irons 2' long from Geo. Blass witness.
 Added DNR Mon. buried. P.P. N27°W 41.30'; 18" B. Oak S35°E 65.86' 14" B. Oak S55°W 66.83; Ctr. Sand Rd. S. Due W. 4' Ctr. E-W Sand Rd. N 13'. - LCRC - L. 3, P. 76 - C.F. Roser - 1988
 Fd. DNR Mon. - same wit. as L. 2, P. 107 |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

A9 & M9 - Standard Sec. corner common to Sec. 19 & 30, T19N, R12W and Sec. 24 & 25, T19N, R13W - Excavated Sand Rd. 'T' intersection w/ Robert Wetherell, PS #24624. Find broken thunder mug (Crockery night commode) with one small bottle buried in intersection as per old Co. Surveyor notes. CL on Sand Rd. S is 3' E. CL of E-W Rd. is 8' N. Broken thunder mug accepted as the best available evidence of the position of the original corner.

Reference Pt. 'C' - Fd. broken DNR Alum. cap on 1" x 27" iron pipe w/ 2- 30" long iron fence post on either side per Roser LCRC's - S49°18'E 9.57' of A9 & M9. Position used by Blass to set A10 - M10 by single proportion. Position used by Roser to prorate & set corners to the East. Broken DNR Monument & fence post irons not utilized as A9 - M9 in this survey. Replaced broken DNR Mon. w/ cabin spike & reset fence post irons on either side.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A9 & M9 - Replaced broken thunder mug w/ 4" DOC (DNR)
 Brass cap on 1" x 36" Galv. Iron pipe w/ cap encased w/ conc. - Down 1.5'.
 Placed all broken crockery at base of monument as memorial.
 N59°W 75.90' to set N & T in SW side 7" J. Pine scribed 'XBT'
 N69°E 85.69' to set N & T in NW side 8" W. Pine scribed 'XBT'
 S38°E 75.21' to set spike & tag in NE side 28" B. Oak (CFR)
 S45°W 64.67' to Fd. nail in NW side 20" B. Oak (CFR)
 N19°W 34.09' to set N & T in W side PP
 N 33' to reset Cedar post w/ loc. tag & set Blue Carsonite Post w/ Loc. tag
 S49°18'E 9.57' to cabin spike & fence post irons - Reference Pt. 'C'.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/26/2001