

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Lake Located In Corner Code #
 (County)

1. Public Land Survey		T <u>19N</u>	R <u>12W</u>	B <u>7</u>
		T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____	_____
	S _____	T _____	R _____	_____
3. Miscellaneous Property in Section	S _____	T _____	R _____	_____
	S _____	T _____	R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on August 8, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7	●												
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-7 - G.L.O. Set 1/4 post- S. Sibley-1838
 Pine 20" N06°E 4.73 chains
 - G. H. Johnson-1912- survey of N1/2 of NW 1/4 of sec. 19
 Iron stake. Pitch Pine 12" N31°W 15 on side of hill.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

B-7 - 1/4 corner common to section 18 and 19. Searched extensively of iron stake noted by Johnson but found nothing. Also searched for irons at SW and SE corner of Johnson's survey but found nothing. Did find iron at A7 but it has long history before Johnson's survey. Not sure why we could find no evidence of Johnson's survey. In section 18 find that the N 1/2 of N-S 1/4 line line is monumented by 1" iron pipes at B5 and B6 with a old fence on the line ±. This monumented line is 2640± at right angles and West of the East Line of section 18. The N & S lines of section 18 are nearly 7° off the cardinal direction and quite long from GLO which makes the original survey in this area questionable. Thus making the East 1/2 of section 18 to have 2640' fits GLO for East 1/2 of section 18. Thus set 4" DNR aluminum cap on 1" X 36" galvanized iron pipe by extending line South from monumented B5 and B6 to intersect line between A7 and C7. Top of steep bank to North is 15' North. This maybe side hill Johnson notes. DNR monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7 4" aluminum cap on 1" X 36" iron pipe
 North 1' to set blue carsonite post
 N13°E 25.87' to nail and tag in NE side of 10" twin W. Oak scribed "XBT"
 S45°E 14.96' to Sp. and tag in NE side of 6" W. Pine scribed "XBT"
 S22°W 23.47' to Nail and tag in NW side of 6" twin W. Oak scribed "XBT"
 N54°W 24.87' to nail and tag in SW side of 5" J. Pine scribed "XBT"



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/26/2001