

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In:			
Lake _____	Located In	Corner Code #	
(County)			
1. Public Land Survey	T <u>19N</u> R <u>12W</u>	<u>C6</u>	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on May 1, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4			3			2	1
3													
4	7			8		9			10			11	12
5													
6	18			17		16			15			14	13
7													
8	19			20		21			22			23	24
9													
10	30			29		28			27			26	25
11													
12	31			32		33			34			35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

- C6 - GLO - Set 1/4 post - S. Sibley - 1838  
Hemlock 20" S8°E 23 L.  
Pine 16" N44°W 17 L.
- LCRC - L.2, P.7 - G. Blass - 1972  
Fd. 1/2" iron pipe at intesection of fence from N & W.  
N & C in E side 10" Maple S22°W 12.88'  
N & C in W side 6" Tw. Maple N11°W 47.41'  
N & C in N side 10" Cedar S80°E 35.55'
- Rec. Sur - L.1, P.163 - C. Cole - 1972  
1/2" iron pipe - same wit. as Blass LCRC.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

C6 - 1/4 corner common to Sec. 17 & 18 - Fd. 3 1/4" George Blass Brass cap on 4" round conc. mon. Fits 3 Blass witnesses Cedar & Tw. Maple in poor condition but a live. Remains of fence N & W. No evidence of GLO BT's. Lots of large W. P. Stps. in area but no marking. Previous DNR survey measured N 1395'+ vs. 1399' - GLO to S. edge of Little Manistee River. Conc. Mon. is close to midway & on line between C5 & C7. Conc. Mon. accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C6 - 3 1/4" brass cap on 4" Conc. Mon.  
South 1' to set Blue Carsonite Post  
S27°W 12.66' to set N & T in E side 14" R. Maple (GB, CC)  
S88°E 21.38' to set N & T in N side 7" W. Pine scribed 'XBT'  
N52°E 26.11' to set N & T in NW side 8" W. Pine scribed 'XBT'  
S12°E 30.36' to set N & T in W side 6" W. Pine scribed 'XBT'



Signed by: Craig W. McVean  
Surveyor's Michigan License No.: 39088

Date: 11/26/2001