

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Lake \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County) \_\_\_\_\_

1. Public Land Survey T 19N R 12W D1  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling in Section S T R  
S T R  
3. Miscellaneous Property in Section S T R  
S T R

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on May 1, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

D1 – GLO- Not set in original survey  
- LCRC – L. 2 pg. 221 – C.F. Roser - 1974  
Set DNR Mon. & Cedar post per standard BLM instructions  
5" Maple N88°E 12.9'  
12" W. Pine N55°E 57.9'  
S. ¼ sec. 32 (20-12) S89°04'W 33.28'  
- DNR Survey projects 70-41 (1975)  
& 78-41 (1980) – C.F. Roser

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

D1 – Closing ¼ corner common to sec. 5, T19N, R12W – Fd. 4" DOC. (DNR) Alum. cap on 1" Iron pipe per Roser. W. Pine NE. BT. is dead & Maple is gone. Roser indicates on his survey map 70-41 (1975) that corner was set single proportion. DOC. Mon. is a split of Eastings between C1 & E1.  
DOC. (DNR) Mon. accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D1 – DOC (DNR) Mon. on 1" Iron Pipe. Add ring of stone  
C/L of E-W trail bridge is 10' N  
SE 1.4' to face fd. cedar post  
NE 1' to set Blue Carsonite Post  
N88°E 79.45' to set N&T in N. side 16" W. Pine scribed 'CCBT'  
N73°E 125.14' to set N&T in S. side 30" W. Pine scribed 'CCBT'  
N8°W 4.25' to set N&T in S. side E-W Bridge timber support  
West 33.53' to DOC (DNR) Mon. in stream at C13, T20N, R12W



Signed by: Craig W. McVean  
Surveyor's Michigan License No.: 39088

Date: 11/26/2001