

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Lake _____ (County) _____	Located In _____	Corner Code # _____
1. Public Land Survey	T <u>19N</u> R <u>12W</u>	<u>E4</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on October 4, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	●	9	10	11	12						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E4 - GLO - Set 1/4 post - S. Sibley - 1838
 Pine 10" N22°E 36 L.
 Pine 10" S38°W 52 L.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

E4 - 1/4 corner common to Sec. 8 & 9 - Could find no GLO evidence or other evidence. Set 4" DNR Alum. cap on 1" x 36" Galv. Iron encased in 4" x 1' long PVC pipe filled w/ conc. around cap by single proportion between E3 & E5. This position fits previous section work in Sec. 8 by G. Blass & C. Cole who calculated SP position. CL of N-S Sand Rd. is 18' W. DNR Mon. accepted as a careful & faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E4 - 4" DNR AC on 1" x 36" iron pipe with 4" x 1' PVC w/ conc. around cap - buried.
 North 1' to set Blue Carsonite Post
 S80°W 82.34' to set N & T in S side 10" W. Pine scribed 'XBT'
 S50°E 54.81' to set N & T in SW side 10" R. Pine scribed 'XBT'
 N57°E 77.84' to set N & T in SE side 15" scribed 'XBT' - R. Pine
 N5°E 36.38' to set N & T in W side 8" W. Oak - 'XBT'



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/26/2001