

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
LAKE

Located In: \_\_\_\_\_ Corner Code #/ #

1. Public Land Survey T 19 N R 13 W

2. Property Controlling in Section S 35 T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S 35 T \_\_\_\_\_ R \_\_\_\_\_

\_\_\_\_\_ 1, 3

\_\_\_\_\_ 352.5' E

\_\_\_\_\_ OF T-12

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, CARL F. ROSER, in a field survey on JUNE 18, 19 84  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

<p>1  ESTABLISH NW COR, NE 1/4, NW 1/4, SEC 35 PER STD BLM INSTRUCTIONS. COR FITS LAKE-STATE SUBDIVISION OF NW 1/4, SEC 35.</p>	<p>3  ESTABLISH NW COR, SW 1/4, NW 1/4, SEC 35 PER STD BLM INSTRUCTIONS. COR FITS LAKE-STATE SUBDIVISION OF NW 1/4, SEC 35.</p>	<p>4  ESTABLISH NW COR, E 60 ACRES W 1/2, SW 1/4, SEC 35.</p>
---	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>DROVE 5/8" RE-ROD W/RLS CAP.  10" W OAK N 30°E 34.74'  10" R PINE S 15°E 29.87'  10" R PINE S 35°W 38.38'  CTR E-W RD DUE S 4'  FD 1/2" IRON W/RLS CAP;  ADDED CED POST W/LOC TAG, DUE S 33.00'  FD 1/2" PIPE S79°23'E 20.04'</p>	<p>DROVE 5/8" X 3/4" RE-ROD W/RLS CAP.  5" B OAK N 75°W 28.17'  7" W OAK N 45°E 36.72'  6" B OAK S 50°E 22.90'  CTR N-S BIT RD DUE W 3.5'  SET CED POST W/LOC TAG, DUE E 33'</p>	<p>DROVE 5/8" RE-ROD W/RLS CAP;  SET CED POST W/LOC TAG.  3" MAPLE N 70 W 18.1'  3" MAPLE S 30 E 8.5'  3" MAPLE S 75 W 16.1'  CTR TRAIL SE-NW, DUE E 24'</p>
--	--	--



Signed by Carl F. Roser Date 3-18-88

Surveyor's Michigan License No. 12028