

JAN 25 2001

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

SECTION

For corners in
Lake _____

Located in: Corner Code#

- 1. Public Land Survey

T 19 N	R 13 W	A-10 ✓
T 19 N	R 14 W	M-10
T	R	
T	R	
- 2. Property Controlling in Section

S	T	R
S	T	R
- 3. Miscellaneous Property in Sec.

S	T	R
S	T	R
- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

RECORDED
LAKE COUNTY, MI.
LIBER 004 PAGE 0273
Dec 8 04 28 AM '00

Robert L. Wetherell
REGISTERED DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on February 23, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A-10 - W. 1/4 Corner Sec. 30, T19N, R13W
M-10 - E. 1/4 Corner Sec. 25, T19N, R14W

- A. Description of original monument and accessories and/or subsequent restoration:**
- 1837 - Mullet & Brookfield, G.L.O.
 - #1 - 18" Y. Pine N9°W 48 Links
 - #2 - 20" W. Pine S85°W 21 Links
 - 1965 - R.A. Griffin, LS 13584
 - L.C.R.C. - Liber 01, Pg. 247.
 - Found 5" Square rotted wood stake and stumps of both U.S. witnesses. Set 5" Square Concrete Monument.
 - #3 - 4" W. Oak N43°E 49.30'
 - #4 - 5" W. Oak S48°E 50.22'
 - #2 - 20" W. Pine Stump S85°W 15.20'
 - #5 - 4" W. Oak S88°W 33.62'
 - #6 - 9" R. Oak N15°W 62.81'
 - #1 - 18" R. Pine Stump N9°W 33.70'

- B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:**
- I found the 5" Square Concrete Monument by Griffin 187 feet more or less East of a North and South trail road.
- Condition of the accessories are as follows: #1 Found Stump, #2 Found remains of stump #3 Found in good condition, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- I accepted the 5" Square Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful perpetuation of the position of the original corner.

- 14" R. Oak N12°W 62.81' (dock spike in W. side) #6
- 7" W. Oak N89°W 33.56' (dock spike in S. side) #5
- 10" W. Oak N45°E 49.34' (60d spike S. side) #3
- 7" W. Oak S47°E 50.21' (dock spike E. side) #4
- 18" R. Oak S41°W 37.88' (60 spike N. side)

RATIFIED BY _____ CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN *RW*
DATE *12-5-2000*



Signed by *Robert L. Wetherell*

Date December 6, 2000

Surveyor's Michigan License No. 24624