

JAN 25 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

| | | |
|---------------------------------------|---------------|--------------|
| For corners in Lake | Located in: | Corner Code# |
| 1. Public Land Survey | T 19 N R 13 W | B-11 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
| 4. Lot No. _____ Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

RECORDED RECORD
LAKE COUNTY, LAKE COUNTY
LIBER 004 PAGE 0276
DEC 8 11 21 AM '00 11 21
Robert L. Wetherell
REGISTER OF DEEDS REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Robert L. Wetherell, in a field survey on February 23, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

B-11 - 1/4 Corner common to Sections 30 & 31, T19N, R13W

A. Description of original monument and accessories and/or subsequent restoration:

1838 - S. Sibley, G.L.O.
#1 - 8" Pine N57°W 14 Links
#2 - 8" Pine S39°E 17 Links

1986 - K. Ross, LS 17634
Survey recorded Liber 03, Pg. 42
(Set 5" Concrete Monument)
Set corner on line between the N.E. corner and N.W. corner at prorated G.L.O.
#3 - 11" W. Oak S88°W 121.62'
#4 - 11" B. Oak S8°E 21.08'
#5 - 5" R. Pine N40°E 73.56'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the 5" Square Concrete Monument set by Ross.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I accepted the 5" Square Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

10" W. Oak N88°W 121.53' (60d spike in N. side) #3
12" B. Oak S05°E 21.06' (60d spike in E. side) #4
7" R. Pine N44°E 73.57' (60d spike in E. side) #5
8" R. Pine N36°W 67.02' (60d spike in N.E. side)

ATTESTED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN *RJW*
DATE *12-5-2000*

Signed by *Robert L. Wetherell*

Date December 6, 2000

Surveyor's Michigan License No. 24624

