

JAN 25 2001

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

SECTION

For corners in Lake _____	Located in:	Corner Code#
1. Public Land Survey	T 19 N R 13 W C-9	
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____ Recorded Plat _____		
5. Private Claims _____		

RECORDED
LAKE COUNTY, MI.
LIBER 004 PAGE 0274
Dec 8 11 21 AM '00
Shelley Myers
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Robert L. Wetherell, in a field survey on February 23, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

C-9 - Section corner common to Sections 19, 20, 29 & 30, T19N, R13W

A. Description of original monument and accessories and/or subsequent restoration:

1838 - S. Sibley, G.L.O.
20" Pine for the corner.

1922 - Lee McCrimmin
Monument - Iron.
#1 - 12" W. Oak S37°E 129.5'
#2 - 8" W. Oak N50°E 150.5'

1977 - R.A. Griffin, LS 13584
L.C.R.C. - Liber 02, Pg. 312.
"Found 1/4" x 2" x 18" truck spring and witnesses by McCrimmin".
Set 5" Square Concrete Monument
#3 - 5" W. Oak S72°E 24.08'
#4 - 7" W. Oak S12°W 49.56'
#5 - 6" W. Oak S70°W 35.20'
#6 - 4" Post North 1.05'

1986 - K. Ross, LS 17634
L.C.R.C. - Liber 03, Pg. 36
Survey recorded Liber 03, Pg. 48.
"Same accessories as Griffin's in 1977."

1989 - S. Barnett, LS 16923
Survey recorded Liber 03, Pg. 183.
"Same as Griffin's in 1977".

B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:

I found a 5" Square Concrete Monument.

Condition of the accessories are as follows: #1 Found in good condition (S34°E, 128.2'), #2 Gone, #3 Found in good condition, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I accepted the 5" Square Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

12" W. Oak S14°W 49.50' (found dock spike in E. side) #4
6" W. Oak S69°E 24.12' (found dock spike in S. side) #3
8" W. Oak S74°W 35.06' (found dock spike in N. side) #5
9" Tw. W. Oak N16°E 46.32' (60d spike in W. side)

Signed by

Robert L. Wetherell

Date December 6, 2000

Surveyor's Michigan License No. 24624

