

SLU 8 3 1998

ELIOTON

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 0171

For corners in
Lake _____

(County)	Located In:		Corner Code # E-7
	19N	13W	
1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	T	R	_____
2. Property Controlling in Section	S	R	_____
	S	R	_____
3. Miscellaneous Property in Sec.	S	R	_____
	S	R	_____

REGISTER OF DEEDS
 DICKINSON H. ANDREWS
 OCT 29 4 40 PM '98
 LAKE COUNTY, MI.
 RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Robert L. Wetherell June 10, 98

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-7 - Section corner common to Section 16, 17, 20 & 21, T19N R13W, Lake Co., Mi.

- | | | |
|------------------------------------|------------------------------|---------------------------------|
| 1838 - S. Sibley, G.L.O. | Undated Co Sur. Records | 1986 - K. Ross, LS 17634 |
| #1 - 14" Pine S23°E 31 Links | #5 - 10" W. Oak N26°W 55' | L.C.R.C. - Liber 03, Pg. 35 |
| #2 - 16" Pine N5°W 41 Links | #6 - 8 B. Oak S39°E 34' | Found 3/4" pipe - Replaced with |
| 1878 - L.S. Cobb | 1941 G. Blass, LS 5489 | 5" Square Concrete Monument |
| #3 - 20" Y. Pine S44°W 47 Links | Found 3/4" Pipe | #10 - 14" B. Oak S61°W 55.85' |
| #4 - 28' Y. Pine N10°30'W 73 Links | #7 - 16" B. Oak N56°E 37.70' | #11 - 12" B. Oak N44°W 58.36' |
| | #8 - 14" B. Oak S38°W 36.40' | #12 - 11" B. Oak N46°E 46.65' |
| | #9 - 10" B. Oak S28°E 84.30' | #13 - Carsonite Post - West 33' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 - Section corner common to Section 16, 17, 20 & 21, T19N R13W, Lake Co., Mi.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
 IN ACCORDANCE WITH P.A. 345
 CHAIRMAN R. H. W.
 DATE 10-27-98

I found Ross's 5" Square Concrete Monument.

Condition of the accessories are as follows: #1 Gone #2 Gone, #3 Gone, #4 Gone #5 Gone #6 Gone, #7 Found in good condition, #8 Found Stump, #9 Found Stump, #10 Found in good condition, #11, Found in good condition, #12 Found in good condition, #13 Gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 - Section corner common to Section 16, 17, 20 & 21, T19N R13W, Lake Co., Mi.

I accepted the 5" Square Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 14" B. Oak S61°W 55.87' (Found 60d spike in S. side) #10
- 14" B. Oak N45°W 58.26' (Found 60d spike in S.W. side) #11
- 12" B. Oak N74°E 45.52' (Found 60d spike in S.W. side) #12
- 13" B. Oak S25°E 83.95' (Set 60d spike in W. side) #9

Signed by Robert L. Wetherell
 Surveyor's Michigan License No. 24624

Date 10-29-98

