

NOV 21 1997

LIBER 004 PAGE 0024  
SEP 12 10 30 AM '97

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in \_\_\_\_\_  
COMMISSIONER

*Richard M. Dickson*  
REGISTER OF DEEDS

Lake (County)	Located In:		Corner Code #
	19N	13W	
1. Public Land Survey	T _____	R _____	G-5
	T _____	R _____	
	T _____	R _____	
	T _____	R _____	
2. Property Controlling in Section	S _____	T _____ R _____	
	S _____	T _____ R _____	
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	
	S _____	T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on April 3, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-5 - Section corner common to Sections 9, 10, 15 & 16, T19N, R13W, Peacock Twp., Lake Co., Mi.

- |                                      |  |   |
|--------------------------------------|--|---|
| <u>1838 - S. Sibley, G.L.O.</u>      | <u>1939 - Harden - U.S.F.S. Forester</u> | <u>1966 - Robert L. Griffin, LS 13584</u> |
| #1 - 12" Pine N78°E 37 Links         | Iron Bolt                                | L.C.R.C. - Liber 01, Page 156             |
| #2 - 14" Pine S72°W 7 Links          | #3 - 16" R. Oak N59°E 73.75'             | Found Iron Bolt - Replaced with           |
|                                      | #4 - 9" R. Oak S14°E 53.5'               | 5" Concrete Monument                      |
| <u>Undated County Surveyors Book</u> |  | #5 - 9" B. Oak N56°E 95.24'               |
| 2' Long Bolt                         |  | #6 - 5" W. Oak S50°E 96.60'               |
| #3 - 12" B. Oak N57°E 73.0'          |  | #7 - 5" W. Oak S51°W 144.89'              |
|                                      |  | #8 - 5" Maple N17°W 131.29'               |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 - Section corner common to Sections 9, 10, 15 & 16, T19N, R13W, Peacock Twp., Lake Co., Mi.

I found a 10" dock spike directly over a 5" x 36" Concrete Monument in the center of East and West road and on the East edge of road to South.

Condition of accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Found in good condition, #6 Found in good condition, #7 Found in good condition, #8 Found in poor condition.


Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 - Section corner common to Sections 9, 10, 15 & 16, T19N, R13W, Peacock Twp., Lake Co., Mi.

I accepted the 5" x 30" Concrete Monument as a substantial marker, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 10" W. Oak S48°E 96.55' (dock spike in S.W. side) #6
- 10" W. Oak S57°W 144.87' (dock spike in S.E. side) #7
- 15" B. Oak N58°E 95.26' (dock spike in N.W. side) #5
- 8" W. Oak N45°W 109.27' (60d spike in N.E. side)

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP  
IN ACCORDANCE WITH P.A. 345  
CHAIRMAN R.L.W.  
DATE 8-27-97



Witnessed by Robert L. Wetherell  
Surveyor's Michigan License No. 24624