

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:		Located In		Corner Code #
Lake _____ (County) _____				
1. Public Land Survey		T <u>19N</u> R <u>13W</u>		<u>1-9</u>
		T _____ R _____		_____
2. Property Controlling in Section	S _____	T _____ R _____		_____
	S _____	T _____ R _____		_____
3. Miscellaneous Property in Section	S _____	T _____ R _____		_____
	S _____	T _____ R _____		_____
4. Lot No: _____		Recorded Plat: _____		
5. Private Claims: _____				

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Craig W. McVean, in a field survey on June 19, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1-9 - GLO- Set Post S. Sibley- 1838
Pine 30" S13°E 43L. Pine 12" N57°W 43L.
- L.S. Cobb- 1878
Y. Pine 20" N62½°E 111 L. W. Pine 16" S48½°E 41L.
- R.H. Hollister -1905
found old witnesses & set stone at this corner.
- G.H Johnson - 1925-Stone
B. Oak 10" S78°E 48.2 B. Oak 18" N75°W 64
- MDOT- 1930 Proj. M043-12 15.3' Rt. Sta. 289+70- Stone
N53°E 79.3' Bent Spike in 12" Tw. Oak
N73°W 64.1' Bent Spike in 14" Oak
S60°E 48.1' Bent Spike in 12" Oak
- G. Blass -1952 - Stone from highway Survey of 1932 removed
placed Old wagon sheave (axle) from highway wits of 1932
18" B. Oak N73°W 64.10' (OBT) 8" W. Oak N33°E 57.00'
14" B. Oak S60°E 48.10' (OBT) 12" W. Oak S44°E 51.55'

- LCRC - L. 2, Pg. 54 - R.A. Griffin - 1972 - in 1966 Fd. wagon Skein raised to surface with 5/8" sq. boat spike. This corner is 14.8' E of apparent C/L M-37. Fd Stp. of One of Cobb's BT's both Johnson BT's, 3-MDOT BT's & 4 Blass BT's in agreement w/ skein. Replaced wagon Skein w/ 5" sq. X 3' Long conc. post w/ 3" Brass Cap (stamp) 10" dock spike in the SE side 5" Maple scribed 'BT'; N56°E 91.35'; 10" dock Spike in SW side 7" W. Oak scribed BT. S51°E 110.53'; W 66' Metal USFS post X cut in top of a stone (2.5' long X 1.8' wide X 0.8 up) N37°W 125.74'
- LCRC - L. 3, Pg. 52 - C.F. Roser - 1988- Fd. F.S. capped conc. mon.- buried 1' - fit 3 USFS wit & 1 Blass wit.
9" W. Oak S50°E 110.53' 6" Maple N55°E 91.35'
'X' on top 2.5' X 2' stone N40°W 125.7' C/L M-37 W 15'
C/L Dirt Rd. E - due S. 9'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

- 1-9 - Sec. corner common to section 22, 23, 26, & 27 - found 3" USFS brass cap (properly stamped) on concrete post in mon. box - 14.8' E of apparent curve C/L of M-37 at position perpetuated by Cobb, Hollister, Johnson, MDOT, Blass, Griffin & Roser. USFS Mon. accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1-9 - USFS Brass Cap conc. Monument in mon. box
N45°E 50.00' to set Blue carsonite post with location tag
West 66' to Fd. steel post with USFS tag (RAG)
S52°E 110.57' to Fd. spike in SW side 12" W. Oak (RAG,CFR)
N55°E 91.45' to Fd. spike in SE side 7" R. Maple (RAG,CFR)
N40°W 125.22' to Fd. Chiseled 'X' on top 2.8' X 1.8' X 0.9' (up) Granite stone (RAG,CFR)
N33°E 57.60' to set N&T in W. side 14" W. Oak (GB)



Signed by:

Craig W. McVean

Date 11/26/2001

Surveyor's Michigan License No.:

39088