

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:			
<u>Lake</u>	Located In	Corner Code #	
(County)			
1. Public Land Survey	T <u>19N</u> R <u>13W</u>	<u>K-6</u>	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on May 17, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14	●	13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<p><u>K-6</u> - GLO - set 1/4 post - S. Sibley - 1838 Pine 10" N45°W 9 L. Pine 10" S31°E 8 L. - G. Blass - 1960 - Corner location found by retracement survey by George Blass - Sept. 1941 for Mr. Claney in Sec. 13. 3/4" pipe; 14" B. Oak N11°E 46.80'; 16" B. Oak S78°W 100.00'; 8" J. Pine S38°W 35.30'; 6" B. Oak S73°E 41.45'</p>	<p>-DOC(DNR) Cor. Rec. - C.F. Roser - 1969 fd. 3/4" Pipe recovered by G. Blass in 1941. replaced w/ standard dept. mon. 9" J. Pine S40°W 35.3'; 4" Oak N40°W 51.7'; 18" Oak N10°E 46.9'; 6" Oak S75°E 41.3'</p>
--	---

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

K-6 - 1/4 Corner Common to sec. 13 & 14 - Fd. 4" Doc. Alum. cap on 1" Galv. iron pipe per Roser. Fd. stp's of all of Blass and Roser's BT's in agreement with monument. Dept of Conservation monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 - 4" DOC (DNR) Alum. cap on 1" Iron pipe
 SW 1' to set Blue Carsonite Post
 N16°W 9.49' to set N&T in W. side 4" J. Pine
 N85°E 13.76' to set N&T in S. side 7" J. Pine scribed 'XBT'
 S41°E 37.91' to set N&T in SW. side 6" J. Pine scribed 'XBT'
 S8°W 24.19' to set N&T in W. side 6" J. Pine scribed 'XBT'



Signed by: Craig W. McVean Date 11/26/2001
 Surveyor's Michigan License No.: 39088