

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Lake Located In Corner Code #
 (County)

1. Public Land Survey T 19N R 13W L6
 T _____ R _____
 2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
 3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on June 5, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L6 - G. Blass Survey Sec. 13 - 1967 Show calculated position
 - DNR Sur. Proj. #68-31 - C.F. Roser. Show calculated position.
 - Rec. Sur. - L. 2, P. 291 - R.L. Wetherell - 1978 Set Survey marker.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L6 - C ¼, Sec. 13 - Fd. ½ x 18" Rebar w/ cap #17615 - 19305 - 24624 - per record survey that fits Blass & Roser's calculated positions. This capped iron is based on the intersection of ¼ lines using a calculated position at L7 (S ¼ Cor. Sec. 13) that is S86°35'W 18.39' from the accepted L7 position being a DNR monument set at L. S. Cobb's 1878 position. Thus the true calculated intersection of the ¼ lines is S84°38'E 9.17' from Wetherell's CIR. The N1/2 of Sec. 13 has been extensively monumented based on Blass 1967 & Roser's 1968 Surveys. Could not justify moving Wetherell's L6 position since it would disrupt 30 year old monumentation in N ½ of Sec. 13 and thus it is in the public's best interest to accept the existing ½" CIR as the best available evidence of the position of the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L6 - Replaced ½" x 18" CIR # 17615 - 19305 - 24624 w/ 2" Alum.
 Cap on 5/8" x 34" Rebar.
 SW 1' to set Blue Carsonite post w/ loc. tag
 S58°E 4.35' to set N & T in SW side 11" J. Pine
 N30°W 8.78' to set N & T in SW side 3" J. Pine
 S78°W 42.71' to set N & T in SE side 17" Oak
 S34°W 50.51' to set N & T in NW side 18" Oak



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/26/2001