

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Lake _____ (County) _____	Located In T <u>19N</u> R <u>13W</u> <u>L-7</u> T _____ R _____ _____	Corner Code # _____ _____ _____
1. Public Land Survey	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on May 8, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| <p><u>L-7</u> – GLO- Set ¼ Post -S. Sibley- 1838
 Pine 8" N15°E 18L. Pine 10" S9°W 24L..
 - L.S. Cobb- 1878 – Set ¼ post-iron, glass & crockery.
 P. Pine 10" S13 ½ °W 13L. P.Pine 10" N6½ °E 34L.
 - G. N. West - 1908 – fd. Stake Set by Cobb 1878. Iron,
 Glass & Crockery; NBT J. Pine 10" N23½ °E 198L
 J. Pine 10" S13½°E 13L.</p> | <p>- G. Blass – 1941- 1967 surveys show position for corner midway &
 on line between section corners E & W.
 - DNR Survey Project # 68- 31- C.F. Roser – 1968-Comp ¼ Cor.
 per Blass surveys
 - Rec. Survey – L.1, Pg. 480 – P.A. Salisbury – 1972- Nail 12" Oak
 N 33.07': Nail 10" Pine S5°E 14.95' ; Nail 10" Pine S80°W 50.48'</p> |
|--|---|

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L-7 – ¼ Corner. common to sec.13,& 24, - Fd. Pine stake remains, 5 pieces of iron and many pieces of glass & crockery per Cobb & West during joint excavation with Robert Wetherall, PS # 24624. Cobb's position is nearly midway & on line Between his positions at K7 & M7. Cobb's pine stake remains with iron, glass & crockery accepted as the best available evidence of the position of the original corner.

Reference Pt. 'B' - Fd. ½ " rebar that fits remains of Salisbury wits – S83°20' W 18.98' from L7. This ½" rebar closely fits Blass & Roser's calculated position which is based on SP position between M7 (Cobb) and Reference Pt. 'A' being 1" iron pipe that is S82°18'W 37.61' from Cobb's position at K7. ½ " rebar is not utilized as L7 in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 – Replaced pine stake with 4" DNR Alum. Cap on 1" x 36" Galv. iron pipe. Placed all Fd. iron , glass & crockery at base of Monument as a memorial. Add ring of stone.
 North 1' to set blue Carsonite post
 N48°E 45.32' to set N&T in NW side 6" W. Oak scribed 'XBT'
 S46°W 37.11' to set N&T in W side 9" J. Pine scribed 'XBT'
 N83°W 99.46' to set N&T N. side of. 7" W. Oak scribed 'XBT'
 S31°W 63.48' to set N&T in SE. side 8" J. Pine scribed 'XBT'
 S70°E 61.72' to set N&T in SW side 6" J. Pine scribed 'XBT'
 S83°20'W 18.98' to Fd. ½ " rebar – Ref. Pt. 'B'



Signed by: Craig W. McVean Date 11/26/2001
 Surveyor's Michigan License No.: 39088