

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
 Lake _____ Located In _____ Corner Code # _____
 (County) _____

1. Public Land Survey	T _____	R _____		
	T _____	R _____		
2. Property Controlling in Section	S 13	T 19N	R 13W	5
	S 13	T 19N	R 13W	6
3. Miscellaneous Property in Section	S _____	T _____	R _____	
	S _____	T _____	R _____	

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 23, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

5 - DNR Sur. Proj. #68-31
 C. Roser - 1968
 Set 1" Pipe

6 - DNR Sur. Proj. #68-31
 C. Roser - 1968
 Set 1" Pipe

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

5 - CN 1/16, Sec. 13 -
 Fd. 1" I.D. Iron pipe per DNR survey.
 N 32' to SE Bank of Little Manistee River.
 W. 46' +/- to SE Bank of river.
 1" iron pipe accepted as the best available evidence of the corner.

6 - NE 1/16, Sec. 16
 Fd. 1" I.D. iron pipe per DNR survey.
 1" iron pipe accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5 - 1" Iron pipe
 W 1' to set Blue Carsonite Post w/ loc. tag
 S65°W 25.22' to N & T in S side 7" Ash
 S88°W 41.04' to N & T in S side 12" R. Maple
 SE 0.4' to face Fd. Cedar Post

6 - 1" Iron pipe
 S 1' to set Blue Carsonite Post w/ loc. tag
 S10°W 25.04' to N & T in W side 5" R. Maple
 West 70.26' to N & T in W side 10" W. Pine
 S74°E 21.01' to N & T in N side 6" W. Oak
 East 36.59' to Fd. 1/2" CIR #24624



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/26/2001