

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Lake _____ (County) _____	Located In T _____ R _____ T _____ R _____	Corner Code # _____ _____ _____ _____	
1. Public Land Survey	T _____ R _____ T _____ R _____	_____	
2. Property Controlling in Section	S <u>13</u> T 19N R 13W 12 S <u>13</u> T 19N R 13W 13	_____	
3. Miscellaneous Property in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____	
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on August 15, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

12- Recorded survey L. 2, P. 291 - R.L. Wetherall
-1979- survey marker set

13- Recorded survey L. 2, P. 291 - R.L. Wetherall
-1979- survey marker set

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

12- CS 1/16 sec. 13- Set 2" aluminum cap on 5/8" X 34" rebar midway and online between occupied C 1/4(L6) and S 1/4(L7) of sec. 13 per standard BLM procedure.

13- SE 1/16 sec. 13- Set 2" aluminum cap on 5/8" X 34" rebar per standard BLM procedures.

- Reference point 'F'- Found 1/2" capped iron rod #17615-19305-24624 per Recorded Survey S87°38'W 8.65' of cor. '12'. Couldn't accept this capped iron rod since it is based on rejected position for L7 (reference point 'B')

- Reference point 'G'- Found 1/2" capped iron rod #17615-19305-24624 per Record Survey N83°18'W 4.22' of Cor. '13'. Couldn't accept this capped iron rod since it is based on rejected position for L7 (reference point 'B')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

12- 2" aluminum cap on 5/8" X 34" rebar
SW 1' to set blue carsonite post w/ loc. tag
N59°E 10.18' to nail and tag in SE side of 7" B. Oak
S30°E 14.09' to nail and tag in NE side of 4" Tw. Cherry
N33°W 8.37' to nail and tag in SW side of 9" J. Pine
S83°38'W 8.65' to Reference point 'F' -1/2" CIR

13- 2" aluminum cap on 5/8 X 34" rebar
SE 1' to blue carsonite post w/ loc. tag
S51°E 9.75' to nail and tag in SW side of 5" J. Pine
N38°E 12.74' to nail and tag in NW side of 6" J. Pine
N51°W 11.62' to nail and tag in NE side of 4" Cherry
N83°18'W 4.22' to Reference point 'G'- 1/2" CIR

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 33981

Date: 11/26/2001

