

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Lake (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____	_____
2. Property Controlling in Section	S 14 T 19N R 13W	5
	S 14 T 19N R 13W	CSN1/64
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on May 17, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

5 - G. Blass - 1960  
Set 1/2" iron pipe

CSN 1/64 - G. Blass - 1960  
Set 1/2" iron pipe

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

5 - CN 1/16 Cor. Sec. 14  
Fd. 1/2" I.D. Iron pipe per Blass.  
CL of 3-mile is 34' +/- S'y.  
1/2" Iron pipe accepted as the best available  
evidence of the position of the corner

CSN 1/64 - SW cor. of N 1/2 of SW 1/4 of NE 1/4, Sec. 14,  
T19N, R13W - Fd. 1/2" I.D. Iron pipe per Blass.  
1/2" iron pipe accepted as the best available  
evidence of the position of the corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5 - 1/2" Iron pipe  
NE 1' to set Blue carsonite post w/ loc. tag  
N80°E 17.93' to N&T in S. side 6" J. Pine  
N42°E 39.87' to N&T in SE side 11" B. Oak  
N36°W 64.70' to N&T in SW side 16" W. Oak  
S89°W 23.19' to N&T in N side 7" J. Pine

CSN 1/64 - 1/2" Iron pipe  
NE 1' to set blue carsonite post w/ loc. tag  
N78°E 42.12' to N&T in S. side 12" J. Pine  
N51°E 43.22' to N&T in NW side 14" W. Oak  
N68°W 23.91' to N&T in S. side 9" J. Pine  
S1°W 17.53' to N&T in E side Utility pole



Signed by: Craig W. McVean  
Surveyor's Michigan License No.: 39088

Date: 11/26/2001