

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Lake (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____	_____
2. Property Controlling in Section	T _____ R _____	_____
	S 24 T 19N R 13W	11
	S 24 T 19N R 13W	12
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on August 15, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

11 - Rec. Sur. - L.1, P. 480
P. Salisbury - 1972 - set mon.

12 - Rec. Sur. - L.1, P. 480
P. Salisbury - 1972 - set mon.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

11 - SW 1/16 cor. Sec. 24 - Set 2" Alum. cap on 5/8" x 34"
Rebar per standard BLM procedure.

12 - CS 1/16 cor. Sec. 24 - Set 2" Alum. cap on 5/8" x 34"
Rebar per standard BLM procedure.

Reference Pt. 'I' - Fd. conc. mon. per Rec. Sur. is N77°40'W
20.96' of '11'. Couldn't accept this position since it is based
on rejected Gov't corner positions in Sec. 24. Conc. Mon. not
utilized as '11' in this survey.

Reference Pt. 'J' - Fd. conc. mon. per Rec. Sur. is N61°37'W
5.08' of '12'. Couldn't accept this position since it is based
on rejected Gov't corner positions in Sec. 24. Conc. Mon. not
utilized as '12' in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

11 - 2" AC on 5/8" x 34" Rebar
NW 1' to set blue carsonite post w/ loc. tag.
N32°E 25.13' to N & T in E side 3" W. Pine
S28°W 26.24' to N & T in NW side 10" B. Oak
N70°W 43.84' to N & T in SW side 5" W. Pine
N77°40'W 20.96' to conc. mon. w/ 1/2" iron -
Ref. Pt. 'I'

12 - 2" AC on 5/8" x 34" Rebar
N61°E 15.35' to N & T in NW side 5" W. Pine
S16°E 30.21' to N & T in NW side 4" W. Pine
N50°W 25.07' to N & T in NE side 4" W. Pine
NE 1' to set blue carsonite post w/ loc. tag
N61°37'W 5.08' to conc. mon. w/ 1/2" iron -
Ref. Pt. 'J'

Signed by:

Craig W. McVean

Date:

11/26/2001

Surveyor's Michigan License No.:

39088

