

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Lake _____ (County) _____	Located In T _____ R _____ T _____ R _____	Corner Code # _____ _____ S 24 T 19N R 13W 9 S 24 T 19N R 13W 13 _____ _____ S _____ T _____ R _____ S _____ T _____ R _____
---	--	--

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 30, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24	●	
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

9- None 13- None



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

<p><u>9</u>- CE 1/16, sec. 24 Set 2" aluminum cap on 5/8" X 34" rebar per standard B.L.M. procedure.</p>	<p><u>13</u>- SE 1/16, sec. 24 Set 2" aluminum cap on 5/8" X 34" rebar per standard B.L.M. procedure.</p>
--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p><u>9</u>- 2" aluminum cap on 5/8" X 34" rebar NW 1' to set blue carsonite post with location tag N49°E 15.22' to nail and tag in SE side of 4" B. Oak N44°W 18.18' to nail and tag in SE side of 4" B. Oak S32°W 6.34' to nail and tag in West side of 4" J. Pine S32°E 23.46' to nail and tag in SW side of 2" B. Oak</p>	<p><u>13</u>- 2" aluminum cap on 5/8" X 34" rebar SW 1' to set blue carsonite post with location tag N6°W 45.74' to nail and tag in West side of 7" W. Pine S71°E 11.36' to nail and tag in North side of 4" W. Pine S20°W 38.97' to nail and tag in West side of 6" W. Pine N72°W 12.95' to nail and tag in North side of 4" W. Pine</p>
---	---

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 33981

Date: 11/26/2001