

SURVEY & REMONUMENTATION

MAY 18 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 0121

For corners in
Lake _____

Located In:	Corner Code #
T ^{19N} R ^{14W}	C-1
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

REGISTERED
LAKE COUNTY, MI.
APR 14 3 04 PM '98
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Wetherell, in a field survey on Jan. 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-1 - Section corner common to Sections 5 & 6, T19N, R14W, Sauble Twp., Lake Co., Mi.

1838 - S. Sibley, G.L.O.

- #1 - 12" Beech S49°W 25 Links
- #2 - 10" Beech S74°E 31 Links
- Post for Sections 31 & 32 of T20N, R14W. West 36 Links

1908 - J. W. Nicholson, Co. Sur.

- "Found old stakes and part of witness trees".
- #3 - 24" Pine Snag S30°E 15 Links

1965 - Robert Griffin, LS 13584

- L.C.R.C. - Liber 01, Pg. 173
- "Found rotted wood stake and pine snag by Nicholson in 1908".
- Set 5" Square Concrete Monument
- #4 - 3" B. Oak S73°E 18.82'
- #5 - 6" W. Pine S40°W 28.90'
- #6 - 5" Maple S60°W 57.82'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: #7 - 1" Pipe N87°W 23.76'

(Sec. Cor. of Sec. 31 & 32, T20N, R14W)

C-1 - Section corner common to Sections 5 & 6, T19N, R14W, Sauble Twp., Lake Co., Mi.

I found Griffin's 5" Square Concrete Monument.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Found in good condition, #5 Found in good condition, #6 Gone, #7 Found in good condition.

NOTIFIED BY THE LAKE CO. DEED REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN R.L.W.
DATE 4-9-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 - Section corner common to Sections 5 & 6, T19N, R14W, Sauble Twp., Lake Co., Mi.

I accepted the 5" Square Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful perpetuation of the position of the original corner.

- 11" B. Oak S73°E 18.71' (dock spike in N.E. side) #4
- 16" W. Pine S40°W 28.90' (dock spike in N. side) #5
- 10" Beech N58°E 57.90' (60d spike in N. side)
- 9" cedar N42°W 28.00' (60d spike in N.E. side)
- 3/4" x 24" re-bar with brass cap N86°W 23.76' (Sec. Cor. of 31 & 32, T20N, R14W)

Signed by Robert L. Wetherell
Surveyor's Michigan License No. 24624

Date 4.14.1998

