

SURVEY & REMONUMENTATION

MAY 18 1998

LIBER 004 PAGE 0120

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Lake _____

(County)

Located In:

Corner Code #

1. Public Land Survey

| | | | | |
|---|-----|---|-----|-----|
| T | 19N | R | 14W | C-2 |
| T | | R | | |
| T | | R | | |
| T | | R | | |
| S | | T | | |
| S | | T | | |
| S | | T | | |
| S | | T | | |

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

REGISTER OF DEEDS
Shirley H. Woodard
 APR 14 3 04 PM '98
 RECORDED
 LAKE COUNTY, MI.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert L. Wetherell, in a field survey on Jan. 27, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|---|---|----|---|----|---|----|---|----|---|----|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | ● | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-2 - 1/4 corner common to Sections 5 & 6, T19N, R14W, Sauble Twp., Lake Co., Mi.

1838 - S. Sibley, G.L.O.
 8" Cedar for corner
 2640' to Southwest corner
 2870.34' to Northwest corner

1908 - J.W. Nichoson, Co. Sur.
 "Found no cedar corner tree after diligent search. Set post at edge of swamp on true line".
 #1 - 22" Pine Stump S5°E 60 Links
 Showed distance of 40 Chains (2640') to Southwest Sec. corner and 43.08 chains (2843.28') to Northwest Sec. corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-2 - 1/4 Corner common to Sections 5 & 6, T19N, R14W, Sauble Twp., Lake Co., Mi.

This corner falls in a swampy area that is very wet and lots of wind falls. I made an extensive search and dig, but was unable to recover Nichoson's post or accessory. I set the corner on line between the Section corners and at a proration of Nichoson's distances.

I measured a total distance of 5589.69'
 2691.23 feet to Southwest corner of Section 5,
 2898.46 feet to Northwest corner of Section 5

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
 IN ACCORDANCE WITH P.A. 345
 CHAIRMAN R.L.W.
 DATE 4-9-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-2 - 1/4 Corner common to Sections 5 & 6, T19N, R14W, Sauble Twp., Lake Co., Mi.

I set a 1-1/4" Iron Rod 3 feet long with 8" Cedar Post along side, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 7" Maple N34°W 42.01' (60d spike in W. side)
- 2" White Pine S80°W 25.2' (Center of Tree)
- 5" Cedar S23°W 28.20' (60d spike in E. side)
- 7" cedar S13°E 7.50' (60d spike in E. side)

Signed by Robert L. Wetherell
 Surveyor's Michigan License No. 24624

Date 4-14-98

