

SURVEY & REMONUMENTATION

MAY 18 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 0118

For corners in
Lake _____

Located In: _____ Corner Code # _____

1. Public Land Survey	T ^{19N} R ^{14W}	E-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTERED
LAKE COUNTY, MI.

APR 14 3 04 PM '98

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Wetherell, in a field survey on Jan. 27, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- E-2 - 1/4 Corner common to Sections 4 & 5, T19N, R14W, Sauble Twp., Lake Co., Mi.
 - 1838 - S. Sibley, G.L.O. 1937 - D.S. Hazelton, Co. Sur. 1984 - Clinton Cole, LS 17615
 - #1 - 10" W. Oak N13°E 15 Links Unrecorded map shows corner in Surveyed N.W.1/4-N.W.1/4,
 - #2 - 6" W. Oak S25°W 11 Links West edge of Marsh. Sec. 4. No monument or
 - 1908 - J.W. Nicholson, Co. Sur. accessory given.
 - "Set by measurement on Section Line between Section corners. On West end of marsh. Original corner gone".
 - #3 - 20" Dry Y. Pine S10°E 7-1/2 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-2 - 1/4 Corner common to Sections 4 & 5, T19N, R14W, Sauble Twp., Lake Co., Mi.

I found a 1/2" pipe over top of 1/2" rebar in the West edge of swamp. Corner fits Cole's 1/16 corner to the North. Corner is 40 feet East more or Less of North and South of dirt road.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN R. L. W.
DATE 4-9-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-2 - 1/4 Corner common to Sections 4 & 5, T19N, R14W, Sauble Twp., Lake Co., Mi.

I replaced the 1/2" pipe with a 3/4" x 6' pipe with Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 20" W. Pine N13°E 94.12' (60d spike in N.W. side)
- 13" W. Oak N39°W 145.54' (60d spike in W. side)
- 12" Tw. W. Oak S22°W 108.39' (60d spike in S.E. side)
- 8" Maple S35°E 194.26' (60d spike in W. side)

Signed by Robert L. Wetherell
Surveyor's Michigan License No. 24624

Date 4-14-98

