

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 20 ^{N.} R. 11 ^{W.}	B-1; C-1;
2. PROPERTY CONTROLLING IN SECTION	T. ^{N.} S. R. ^{E.} W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. ^{N.} S. R. ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JULY 8, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-1 RE-ESTABLISHED N 1/4 CORNER OF SEC. 6, T20N-R11W, ON LINE BETWEEN THE NE & NW CORNERS OF S-6 AND AT PRO-RATED DISTANCE TO U.S. (G.L.O. PLAT-RUN-OUT). CORNER FALLS ON SECOND CORRECTION LINE OR TWP. LINE COMM TO T20 & 21N.
- C-1 RE-ESTABLISHED SECTION CORNER COMMON TO SEC'S 5 & 6 ON NORTH LINE OF T20N-R11W AT PRO-RATED DISTANCE TO U.S. (G.L.O.) AND ALSO ON SOUTH LINE OF SEC. 32, T21N-R11W; SECOND CORRECTION LINE. (See working drawings)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1	C-1
SET DNR MON. & CED. POST	SET DNR MON. & CED. POST
2" W. PINE S30°E 38.0'	15" R. PINE S5°W 40.0'
10" W. PINE S15°W 40.8'	14" R. PINE S40°W 54.9'
5" W. PINE S70°W 79.6'	15" R. PINE S65°W 82.8'
FD OLD CED POST	OLD E-W FN DUE S 15' (±3')
W/OLD U.S.F.S. LOC.	
TAG S85°E 38'	

SIGNED BY Carl F. Roser 04-06-82 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ LAKE COUNTY