

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 20 N. S. R. 11 E.	
2. PROPERTY CONTROLLING IN SECTION	T. 20 N. S. R. 11 E.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. 20 N. S. R. 11 E.	115.6'E OF F-13 115.7'E S-33, CODE 12
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on _____, 19____ established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on March 5, 1984, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

115.6'E OF F-13:

DROVE 5/8" X 34" REROD WITH RLS CAP FOR SE COR OF WEST 7-RODS OF SW 1/4 OF SE 1/4 OF SEC. 33. COR FALLS AT COR OF OLD FN'S, FN'S W & N. COR IS S86°12'E, 115.79' FROM S 1/4 COR OF S-33.

115.7'E S-33, CODE 12:

DROVE 5/8" X 34" REROD W/RLS CAP FOR NE COR OF WEST 7-RODS OF SW 1/4 OF SE 1/4 OF SEC. 33. COR FALLS AT COR OF OLD FN'S, FN'S WEST & SOUTH. COR IS S85°58'E FROM NW COR OF SW-SE OF S-33.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

115.6'E OF F-13	115.7'E S-33, CODE 12
SET 5/8" X 34" REROD W/RLS CAP & CED POST W/LOC TAG.	SET 5/8" X 34" REROD W/RLS CAP & CED POST W/LOC TAG.
3" SUG MAP N25°E 9.0'	12" B CHERRY S05°W 9.7
10" W PINE DUE S 7.7'	17" B CHERRY S65°W 15.4
5" SUG MAP S75°W 14.2	10" B CHERRY N35°W 34.0
N'LY EDGE PINE RV DUE S 60'	

SIGNED BY

Carl F. Roser 6/27/84

DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

CHIEF OF SURVEY PARTY

DATE

APPROVED AND SIGNED BY

MICHIGAN REGISTERED LAND SURVEYOR

DATE

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO.

DOVER TWP
LAKE COUNTY

