

MAY 16 1997

REGISTRATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0421

REGISTER OF DEEDS

Signature: M. [unclear]

DEC 16 10 27 AM '96

RECORDED LAKE COUNTY, MI.

For corners in

Table with columns: Lake (County), Located In: (T, R), Corner Code --#

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13

I, Robert L. Wetherell, in a field survey on September 19, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-5 - Section corner common to Sections 7, 8, 17 & 18, T20N, R11W, Lake Co., Mi.

1838 - S. Sibley, G.L.O.
#1 - 28" Hemlock S32°E 25 Links
#2 - 18" Hemlock N34°W 51 Links

1974 - Jim Fletcher (Granger Eng.)
Broke Sections 17 & 18, recovering only the N.W. cor. Sec. 18, the N.E. & S.E. corners Sec. 17. He did not set any other Government corners.

1993 - Robert L. Wetherell, LS 24624
L.C.R.C. - Liber 03, Page 172.
Set 1/2" re-bar in center of East and West road at a prorated distance G.L.O. (G.L.O. vs Meas) between the N.W. cor. Sec. 18 and N.E. cor. Sec. 17.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5 - Section corner common to Sections 7, 8, 17 & 18, T20N, R11W, Lake Co., Mi.

I found the 1/2" Iron that I had set in 1993. In reviewing my computations (for proration) I discovered I had used the wrong G.L.O. distance for prorating. I, therefore, used the correct distance and moved the corner 1.30 feet East of the position I established in 1993.

G.L.O. distance between N.W. cor. Sec. 18 and N.E. cor. Sec. 17 = 10,405.56 feet
Measured distance between N.W. cor. Sec. 18 and N.E. cor. Sec. 17 = 10,397.62 feet

G.L.O. distance between N.E. cor. Sec. 17 and N.W. cor. Sec. 17 = 5277.36 feet
Distance between N.E. cor. Sec. 17 and N.W. cor. Sec. 17 as established = 5273.33 feet

ATTESTED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN DATE 12-12-96 RLW.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5 - Section corner common to Sections 7, 8, 17 & 18, T20N, R11W, Lake Co., Mi.

I set a 3/4" x 24" re-bar with Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 9" R. Pine N48°W 46.21' (60d spike in S.W. side)
10" B. Oak N17°E 20.39' (60d spike in W. side)
10" W. Pine S62°E 64.02' (60d spike in N. side)
8" R. Pine S23°W 75.17' (60d spike in E. side)
7" Cedar Post with U.S.F.S. Tag S02°W 31.1' (to center)

Signed by Robert L. Wetherell
Surveyor's Michigan License No. 24624

Date 12-13-1996

