

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 0153

For corners in
Lake _____
(County)

	Located In:		Corner Code #
	20N	11W	
1. Public Land Survey	T	R	H-9
	T	R	
	T	R	
	T	R	
2. Property Controlling In Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

SURVEY & REMONUMENTATION
FEB 16 1999
SECTION

REGISTER OF DEEDS
Shirley M. Adams

OCT 29 4 39 PM '98

RECORDED
LAKE COUNTY, MI.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Robert L. Wetherell June 4, 98

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	

A. Description of original monument and accessories and/or subsequent restoration:

H-9 - 1/4 Corner common to Sections 22 & 27, T20N, R11W, Lake Co., Mi.

- | | | |
|-------------------------------|-------------------------------|--|
| 1838 - S. Sibley, G.L.O. | 1922 - G.H. Johnson, Co. Sur. | 1996 - R.L. Wetherell, LS 24624 |
| #1 - 12" Beech N77°E 30 Links | 1" Pipe | L.C.R.C. - Liber 003, Pg. 424. |
| #2 - 10" Beech N43°W 32 Links | #3 - Pine Stump N47°E 34' | Set 1/2 re-bar on line between Section corners at distances prorated to Johnson's 1922 Survey. |
| | N.E. cor. Sec. 27 - 2612.8' | #4 - 6" cherry N8°W 96.20' |
| | N.W. cor. Sec. 27 - 2651.2' | #5 - 5" Tw. Maple N29°E 87.76' |
| | Culvert 253' - West | #6 - 6" R. Oak N52°E 77.17' |
| | | #7 - Power Pole S68°E 69.14' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345,
CHAIRMAN R. R. W.
DATE 10-27-98

H-9 - 1/4 Corner common to Sections 22 & 27, T20N, R11W, Lake Co., Mi.

I found the 1/2" capped re-bar I set in 1996. The corner is 13 feet South of the centerline of an east and West road and 15 feet East of driveway South. I measured 249 feet West to a small creek running under road. Distance to the Northeast corner Section 27 is 2607.81 feet. Distance to Northwest corner Section 27 is 2646.13 feet.

Fits occupational fence 503 feet to the South.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition, #7 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 - 1/4 Corner common to Sections 22 & 27, T20N, R11W, Lake Co., Mi.

I replaced the 1/2" re-bar with a 3/4" x 24" re-bar with Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 6" Cherry N8°W 96.20' (60d spike in E. side) #4
- 5" Tw. Maple N29°E 87.76' (60d spike in W. side) #5
- 6" R. Oak N52°E 77.17' (60d spike in N.W. side) #6
- Power Pole S68°E 69.14' (P.K. nail in N. side) #7

Signed by Robert L. Wetherell
Surveyor's Michigan License No. 24624

Date 10-29-98

