

JAN 25 2001

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

**RECORDED
LAKE COUNTY, MI.**

SECTION

**LIBER 004 PAGE 0230
MAY 5 10 24 AM '00**

Shelley Meyers
REGISTER OF DEEDS

For corners in Lake _____	Located in:	Corner Code#
1. Public Land Survey	T 20 N R 11 W	K-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____ Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on March 20, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

K-11 - Section corner common to Sections 25, 26, 35 & 36, T20N, R11W

A. Description of original monument and accessories and/or subsequent restoration:

1838 - S. Sibley, G.L.O.

- #1 - 14" Elm N44°E 55 Links
- #2 - 8" Beech S32°W 34 Links

1919 - G.H. Johnson, Co. Sur.

- 1 ¼" Pipe
- #3 - 12" Maple N11°W 165'
- #4 - ¼ Corner North = 2622'
- #5 - ¼ Corner East = 2605'

1999 - M. McClung, LS 13037

Survey recorded Liber 04, Pg. 280.
"Found 2 corners approximately 3.3' apart used the W. corner (1 ½" Pipe)."
#5 - Measured 2602.22' East

B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:

I found a 1 ¼" Pipe 1 foot West of centerline of North-South road and in line with roads East and West. I also found a ¾" iron pin 3 feet more or less East of the 1 ¼" pipe. I accepted the 1 ¼" pipe because I believe it to be the corner Johnson used in 1919. I removed the ¾" iron pin. I measured a distance of 2634.6 feet to the ¼ corner West.


Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Measured 2618 feet more or less, #5 Did not measure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1 ¼" pipe with a ¾" x 24" rebar with Lake County Remon Cap, and is accepted as a careful and faith reestablishment of the position of the original corner.

- P. Pole S65°W 189.74' (mag nail S. side)
- Center Tele. Pole S26°E 113.44' (nail N.E. side)
- 6" R. Pine N86°E 176.89' (60d nail N. side)
- 2" Angle Iron Fence Post N47°E 42.49'

VALIDATED BY THE LAKE COUNTY REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN *R.L.W.*
DATE *4-11-2000*



Signed by Robert L. Wetherell
Surveyor's Michigan License No. 24624

Date April 12, 2000