

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>20</u> N. <u>●</u> R. <u>12</u> W. <u>●</u>	D-13;E-13;F-13;G-13
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 21, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories established to perpetuate locating the position of the corner:~~

C. (continued) G-13
 Set DNR monument & cedar post
 9" Maple N50°W 7.9
 12" Ash N20°E 36.5
 NE Sec. 4 N89°54' E 49.50

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-13 Restored corner in 8' wide stream, ~~center~~ ^{COURSE} southerly, and from white pine stump (B.T.) per witness and calls in U.S. line notes. Monument consists of DNR cap on 6' of 1" pipe on 6' of 1½" pipe.
- E-13 Restored corner per standard B.L.M. instructions.
- F-13 Restored corner per standard B.L.M. instructions.
- G-13 Restored corner at U.S. distance west of found NE corner of Sec. 4, T.19N., R.12W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13	E-13	F-13
Set DNR monument & cedar post in stream	Set DNR monument (buried)	Set DNR Monument & cedar post
12" W. Pine N16°W 91.2	3" W. Pine N40°W 61.4	8" J. Pine N63°W 33.9
N¼ Sec. 5 (19-12) N89°04'E 33.3	4" W. Pine N40°E 67.7	9" Cherry N07°E 10.2
	Set cedar post w/loc. tag	Found iron S40°W 12.3
	Due N 33'	N¼ Sec. 4 (19-12) N89°38'E 42.92
	NE corner Sec. 5 (19-12)	Center E-W Trail Due S 50'
	N89°38'E 36.30	
	Center E-W Trail Rd. Due S 4'	


SIGNED BY Carl F. Roser 8-8-74 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

NORTH NEWKIRK TOWNSHIP
LAKE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____