

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 20 ^{N.} R. 12 ^{W.}	F-9; G-9
2. PROPERTY CONTROLLING IN SECTION 28	T. 20 ^{N.} R. 12 ^{W.}	2; 15
3. MISCELLANEOUS PROPERTY IN SECTION	T. ^{N.} S. R. ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on January 9, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-9 Restored corner by double proportion per standard B.L.M. Instructions.
- G-9 Found 1 1/4" pipe which fits U.S.B.T. stump remains and stub. DNR monument is aluminum cap on 1"x7 1/2" pipe.
- 2 Established corner per standard B.L.M. instructions.
- 15 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9	G-9	2
Set DNR monument w/1"x7 1/2' pipe & cedar post	Found 1 1/4" pipe, added DNR mon. & cedar post	Set 1"x6' pipe & cedar post w/location tag
8" Cedar N65°E 12.1	12" W. Pine N20°W 24.2	5" Cedar N50°W 10.4
7" Tamarack S88°E 8.0	14" Cedar N35°E 12.7	6" Cedar N80°E 8.9
11" Cedar S50°E 44.5	7" Cedar S60°W 28.4	8" Cedar S20°W 24.8
18" W. Pine stmp. S65°W 34.3		
		15
	Set 1"x30" pipe & cedar post w/loc. tag	
	24" B. Oak N85°E 46.4	
	16" B. Oak Due S 54.5	


SIGNED BY Carl F. Roser 8-8-74 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



NORTH NEWKIRK TOWNSHIP
LAKE COUNTY