

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 20 N. R. 12 W.	C-8; C-9
2. PROPERTY CONTROLLING IN SECTION 19	T. 20 N. R. 12 W.	14
3. MISCELLANEOUS PROPERTY IN SECTION 19	T. 20 N. R. 12 W.	XXX (657.44' S of C-8 & 657.44 N of code 14, Sec. 19)
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 1, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and of subsequent restoration =**

C. (continued)

XXX  
 Set 3/4"x3' pipe  
 22" W. Pine S32°E 75.85  
 12" Oak N72°E 43.7  
 Set cedar post w/loc. tag  
 Due W 16 1/2'

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- C-8 Recovered iron that fits G. Blass witness; corner falls in center of N-S dirt road.
- C-9 Found pipe that fits G. Blass witness and F. Jones witness.
- 14 Established corner per standard B.L.M. instructions. Corner falls in center of N-S sand road.
- XXX Established corner per standard B.L.M. instructions. Corner falls in center of N-S sand road.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-8	C-9	14
Found & accepted 1 1/2" pipe	Found pipe, added 1 1/2" pipe	Set 1"x30" pipe (buried)
9" J. Pine N87°W 36.85	13" J. Pine S60°E 35.8	7" Twn. Maple S83°E 39.6
12" J. Pine N58°E 40.51	14" J. Pine S73°E 28.17	32" W. Pine S40°E 93.43
10" J. Pine S45°E 53.08	7" R. Oak S54°W 70.1	Set cedar post w/loc. tag
Set cedar post w/loc. tag	Set cedar post w/loc. tag	Due W 16 1/2'
Due W 33'	Due E 33'	


SIGNED BY Carl F. Roser 8-8-74 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

NORTH NEWKIRK TOWNSHIP  
LAKE COUNTY