

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. 20 <sup>N.</sup> <input checked="" type="radio"/> R. 12 <sup>W.</sup> <input checked="" type="radio"/>	G-7; H-7; I-7	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION _____	22, T. 20 <sup>N.</sup> <input checked="" type="radio"/> R. 12 <sup>W.</sup> <input checked="" type="radio"/>	1	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> <input type="radio"/> <sup>S.</sup> <input type="radio"/> R. _____ <sup>E.</sup> <input type="radio"/> <sup>W.</sup> <input type="radio"/>		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on June 27, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- G-7 Restored corner on line and at double the distance through 1/8 corner and 1/4 corner to east. Corner falls in gravel road in approximate line with center of road to N & E.
- H-7 Accepted old fence intersection; fence to west and south; which fits 1/8 corner and section corner to west.
- I-7 Restored corner at old fence corner (fence remains N, S & E) which fits two G. Johnson witnesses.
- 1 Recovered and accepted 1" iron pin in line with center of gravel road to west & south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-7	H-7	I-7
Set DNR monument (buried)	Set DNR monument & cedar post	Set DNR monument & cedar post
11" W. Pine S36°W 91.2	14" Maple S15°W 88.1	6" Oak N80°E 20.4
12" W. Pine S55°E 61.20	20" W. Oak N70°E 55.5	9" Maple S48°E 60.1
5" W. Pine N31°E 71.8		5" Maple N32°W 14.2
Set cedar post w/loc. tag	1	
Due S 33'	Found & accepted 1" iron pin	
	4" W. Pine N05°W 27.0	
	11" W. Pine N85°E 33.4	
	Cedar fence post w/loc. tag	
	S85°E 30'	


SIGNED BY Carl F. Roser 8-8-74 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_



NORTH NEWKIRK TOWNSHIP  
LAKE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_