

MAY 18 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Lake _____

Located in: _____ Corner Code # _____

1. Public Land Survey

T	20N	R	12W	B-5
T	_____	R	_____	_____
T	_____	R	_____	_____
T	_____	R	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

REGISTERED
LAKE COUNTY, MI
APR 14 3 05 PM '98
REGISTER OF DEEDS
Register of Deeds Starting File Number

I, Robert L. Wetherell, in a field survey on March 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- B-5 - 1/4 Corner common to Sections 7 & 18, T20N, R12W, North Newkirk Twp., Lake Co., Mi.
- | | | |
|---------------------------------|---|--|
| <u>1838 - S. Sibley, G.L.O.</u> | <u>1964 - G. Blass, LS 5489</u> | <u>1996 - R.L. Wetherell, LS 24624</u> |
| #1 - 8" Pine S71°W 91 Links | Set 1" x 24" Bolt at prorated distance and on line between Sec. corners. Developed plat of "Deer Trail Crossing". | Survey recorded in Liber 04, Pg. 125 |
| #2 - 6" Pine N14°E 61 Links | #3 - 8" B. Oak S45°30'E 35.80' | #6 - 16" B. Oak S2°E 56.20' |
| | #4 - 8" B. Oak S31°W 45.60' | #7 - 18" B. Oak S66°W 77.57' |
| | #5 - 8" J. Pine N40°W 39.21' | #8 - 6' Post N21°W 37.50' |
| | | #9 - P. Pole N62°E 61.48' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5 - 1/4 Corner common to Sections 7 & 18, T20N, R12W, North Newkirk Twp., Lake Co., Mi.
I found a 1" x 24" Bolt 1 foot South of center of East and West road. Distances to Southwest Section corner and Southeast corner fit proration by G. Blass. I measured the following:

2513.90' (measured) to West
2667.80' (measured) to East

HATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN R.L.W.
DATE 4-9-98

Condition of the accessories are as follows: #1 Gone #2 Gone, #3 Found Stump, #4 Found Stump, #5 Gone, #6 Found in good condition, #7 Found in good condition, #8 Found in good condition, #9 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5 - 1/4 Corner common to Sections 7 & 18, T20N, R12W, North Newkirk Twp., Lake Co., Mi.
I replaced the 1" Bolt with a 3/4" x 24" re-bar with Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 16" B. Oak S2°E 56.20' (60d spike in W. side) #6
- 18" B. Oak S66°W 77.57' (60d spike in S.E. side) #7
- P. Pole N62°E 61.48' (P.K. Nail in N.W. side) #9
- 16" B. Oak N32°E 67.44' (60d spike in W. side)

Signed by Robert L. Wetherell
Surveyor's Michigan License No. 24624

Date 4-14-98

