

MAY 18 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 0138

For corners in
Lake _____

Located In:

Corner Code #

(County)

1. Public Land Survey

T^{20N} R^{12W}

E-5

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

S____ T____ R____
S____ T____ R____
S____ T____ R____
S____ T____ R____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Wetherell, in a field survey on March 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RECORDED
LAKE COUNTY, MI.
APR 14 3 05 PM '98
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- E-5 - Section corner common to Sections 8, 9, 16 & 17, T20N, R12W, North Newkirk Twp., Lake Co., Mi.
- | | | |
|---------------------------------|---|-------------------------------------|
| <u>1838 - S. Sibley, G.L.O.</u> | <u>1973 - Clinton E. Cole, LS 17615</u> | <u>1976 - Wm. Ruddell, LS 14769</u> |
| #1 - 8" Pine S4°E 55 Links | L.C.R.C. - Liber 02, Pg. 179 | L.C.R.C. - Liber 02, Pg. 294 |
| #2 - 8" Pine N45°W 70 Links | Found Iron Pin/Set Concrete Monument | Found Concrete Monument |
| | #3 - 8" J. Pine S50°W 61.86' | #4 - 8" J. Pine S.E. 57.63' |
| | #4 - 6" J. Pine S32°E 57.65' | #6 - P. Pole (face) NW 42.95' |
| | #5 - 6" J. Pine N38°W 73.98' | #7 - DNR Post (face) SW 32.68' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5 - Section corner common to Sections 8, 9, 16 & 17, T20N, R12W, North Newkirk Twp., Lake Co., Mi.

I found Cole's 4" Concrete Monument in intersection of roads East, West and North.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition, #7 Gone.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN R.L.W.
DATE 4.9.98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5 - Section corner common to Sections 8, 9, 16 & 17, T20N, R12W, North Newkirk Twp., Lake Co., Mi.

I accepted the 4" Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 7" J. Pine S26°E 57.67' (60d spike in S.W. side) #4
- 11" J. Pine S53°W 61.80' (60d spike in S.E. side) #3
- 10" J. Pine N36°W 73.95' (60d spike in S.W. side) #5
- 9" J. Pine N31°E 49.07' (60d spike in N.W. side)

Signed by Robert L. Wetherell
Surveyor's Michigan License No. 24624

Date 4-14-98

