

RECEIVED
 122 CC 1035
 COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0274

For corners in

Lake (County)	Located In:	Corner Code #
	20N 12W	G-7
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN) RECORDED 14th DAY OF
 COUNTY OF LAKE) 1994 A.D. at
James K. DeWitt 11:30 A.M.
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Robert L. Wetherell, October 27, 1994

I, _____, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- G-7 - Section corner common to Sections 15, 16, 21 & 22, T20N, R12W, North Newkirk Twp., Lake Co., Mi.
 - 1838 - Sylvester Sibley, D.S., G.L.O. 1974 - Carl Roser, L.S. 12028 1977 - Clinton Cole, L.S. 17615
 - #1 - 8" Beech S58-1/2°E 41 Links Set D.N.R. Aluminum cap 1" Mon. pipe using Used Roser's corner to survey the S.E.1/4
 - #2 - 10" Beech N29°W 40 Links 1/8 cor. & 1/4 cor. to the E. (1301.0' of N.E./4, Sec. 21, (LakeState File#2947-77 respectively) 1/8 cor. recovered from a 1912
 - 1912 - George Johnson, Lake Co. Sur. survey by George Johnson. L.C.R.C. Liber 02, Pg.229.
 - #3 - 24" Pine Stump West 14 Links #5 - 11" W. Pine S36°W 91.2'
 - #4 - 20 Pine Stump S44°E 31 Links #6 - 12" W. Pine S55°E 61.2'
 - Reported distance of 2600.4' to #7 - 5" W. Pine N31°E 71.8'
 - S.1/4 cor. of Sec. 15. #8 - Cedar Post South 33'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7 - Section corner common to Sections 15, 16, 21 & 22, T20N, R12W, North Newkirk Twp., Lake Co., Mi.

I found the D.N.R. aluminum capped monument (1-1/4" pipe) at intersection of roads East and North. Condition of the accessories are as follows: #1 gone, #2 Gone, #3 Gone, #4 Gone, #5 Found in good condition, #6 gone, #7 Found in good condition.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
 IN ACCORDANCE WITH P.A. 345
 CHAIRMAN *[Signature]*
 DATE 11/8/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 - Section corner common to Sections 15, 16, 21 & 22, T20N, R12W, North Newkirk Twp., Lake Co., Mi.

I accepted the D.N.R. Capped monument as a substantial monument, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 20" W. Pine S39°W 91.20' (60d spike in N. side of tree) (#5)
- 15" W. Pine N31°E 72.30' (60d spike in W. side of tree) (#7)
- 12" W. Oak S15°W 47.46' (60d spike in E. side of tree)
- 17" W. Pine N86°E 110.81' (60d spike in S. side of tree)

Signed by *Robert L. Wetherell* Date *11/9/94*
 Surveyor's Michigan License No. 24624

