

**SURVEY & REMONUMENTATION**

DEC 4 1999

**LAND CORNER RECORDATION CERTIFICATE**

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

SECTION

For corners in  
Lake

Located in:

Corner Code#

- |   |       |       |      |
|---|-------|-------|------|
| 1. Public Land Survey                   | T 20N | R 12W | G-10 |
|   | T     | R     |      |
|   | T     | R     |      |
|   | T     | R     |      |
| 2. Property Controlling s<br>in Section | T     | R     |      |
|   | S     | T     | R    |
| 3. Miscellaneous<br>Property in Sec.    | S     | T     | R    |
|   | S     | T     | R    |
| 4. Lot No. _____ Recorded Plat          |       |       |      |
| 5. Private Claims                       |       |       |      |

RECORDED  
LAKE COUNTY, MI.  
LIBER 004 PAGE 0234  
DEC 9 9 58 AM '99  
*Shelley Myers*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on October 7, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

G-10 - 1/4 Corner common to Sections 27 & 28, T20N, R12W, Lake Co., Mi.

**A. Description of original monument and accessories and/or subsequent restoration:**

1838 - S. Sibley, G.L.O.  
#1 - 7" Hemlock N37°E 9 Links  
#2 - 18" Maple S11°W 20 Links

1974 - C. Roser, D.N.R.  
L.C.R.C. Liber 02, Page 230.  
Set corner by single proportionate method.  
#3 - 6" Maple S45°E 54.5"  
#4 - 5" Maple N80°W 34.8"  
#5 - 5" Maple S42°W 25.6"

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP  
IN ACCORDANCE WITH P.A. 345  
CHAIRMAN R.L.W.  
DATE 10-19-99

**B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:**

I found the D.N.R. capped monument at the intersection of fence lines East and South. Measurements from a 1979 survey by Lakestate Surveyors & Engineers confirms this single proportionate location.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found Stump, #4 Found in good condition, #5 Found in good condition.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I accepted the D.N.R. Monument as a substantial marker for the corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 7" Maple N71°W 35.14' (60d spike in N. side) #4
- 8" Maple S46°W 25.88' (60 spike in N.W. side) #5
- 7" Triple Maple N20°E 22.43' (60d spike in W. side)
- 6" Maple N60°E 16.20' (60d spike in N. side)
- Cedar Post S.E. 2' more or less

Signed by Robert L. Wetherell

Date 10/22/99

Surveyor's Michigan License No. 24624

