

**SURVEY &  
REMONUMENTATION**

DEC 4 1999

**SECTION LAND CORNER RECORDATION CERTIFICATE**

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

For corners in Lake	Located in:	Corner Code#
1. Public Land Survey	T20N	R12W I-11
	T	R
	T	R
	T	R
2. Property Controlling s in Section	T	R
	S T	R
3. Miscellaneous Property in Sec.	S T	R
	S T	R
4. Lot No. _____ Recorded Plat		
5. Private Claims		

RECORDED  
LAKE COUNTY, MI.  
LIBER004 PAGE0236

DEC 9 9 59 AM '99

*Richard J. Meyer*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Robert L. Wetherell, in a field survey on October 7, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I-11 - Section corner common to Sections 26, 27, 34 & 35, T20N, R12W, Lake Co., MI.

**A. Description of original monument and accessories and/or subsequent restoration:**

1838 - S. Sibley, G.L.O.  
#1 - 6" Ironwood N83 1/2°W 24 Links  
#2 - 6" Ironwood S25°E 11 Links

1935 - G. H. Johnson, Co. Sur.  
Found Iron in Highway  
#3 - 14" Elm N87°E 49'  
#4 - 7" Elm N34°E 43'  
#5 - 4" Maple S47°W 32.5'

1974 - C. Roser, D.N.R.  
L.C.R.C. - Liber 02, Pg. 222  
"Found 1" Iron in centerline of road.  
Fits (3) G. Johnson's witnesses."  
#6 - 23" Maple N28°W 48.53'  
#7 - 6" Maple N68°E 28.27'  
#5 - 19" Maple S45°W 32.71'

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP  
IN ACCORDANCE WITH P.A. 345  
CHAIRMAN R. J. W.  
DATE 10-19-99

**B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:**

I found a 1" x 36" Shaft in line with old fence to East.

Condition of the accessories are as follows: #1 gone, #2 Gone, #3 Gone, #4 Gone, #5 Found in good condition, #6 Found in good condition, #7 Found in good condition.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I replaced the 1" Shaft with a 3/4" x 24" re-bar with Lake County Remon Cap, and is accepted as a careful and faithful reestablishment of the position of the original corner.

30" Maple N24°W 48.60' (60d spike in N.E. side) #6  
24" Maple S50°W 32.60' (60d spike in S.E. side) #5  
7" Maple N68°E 53.32' (60d spike in S. side)  
9" Maple N70°E 28.26' (60d spike in N.W. side) #7

Signed by Robert L. Wetherell

Date 10/22/99

Surveyor's Michigan License No. 24624

