

**SURVEY &  
REMONUMENTATION**

DEC 9 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE**

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

For corners in  
Lake \_\_\_\_\_

Located in:

Corner Code#

- |                                       |       |       |      |
|---------------------------------------|-------|-------|------|
| 1. Public Land Survey                 | T 20N | R 12W | I-12 |
|                                       | T     | R     |      |
|                                       | T     | R     |      |
|                                       | T     | R     |      |
| 2. Property Controlling<br>in Section | T     | R     |      |
|                                       | S     | T     | R    |
| 3. Miscellaneous<br>Property in Sec.  | S     | T     | R    |
|                                       | S     | T     | R    |
| 4. Lot No. _____ Recorded Plat        |       |       |      |
| 5. Private Claims                     |       |       |      |

RECORDED  
LAKE COUNTY, MI.  
LIBER 004 PAGE 0237  
DEC 9 9 59 AM '99  
*Whately Myers*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on October 7, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**I-12- 1/4 Corner common to Sections 34 & 35, T20N, R12W, Lake Co., Mi.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1838 - S. Sibley, G.L.O.  
"6" - Beech for 1/4 Corner."

No record of corner since original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I set the corner in line with fence to the East and on line between Section corners. Corner is 2 feet more or less East of centerline of road. I measured: 2623.12 feet North to Section corner and 2619.34 feet South to Section corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I set a 3/4" x 24" re-bar with Lake County Remon Cap, and is accepted as a careful and faithful perpetuation of the position of the original corner.

- 18" Maple N8°W 104.71' (60d spike in W. side)
- 18" Elm N37°E 46.04' (60d spike in N.W. side)
- 18" Maple S16°W 132.61' (60d spike in E. side)
- 8" Willow S37°W 80.60' (60d spike in S.E. side)

TESTIFIED BY THE LAKE CO. REPR REVIEW GROUP  
IN ACCORDANCE WITH P.A. 645  
CHAIRMAN R.L.W.  
DATE 10-19-99

Signed by

*Robert L. Wetherell*

Date

10/22/99



Surveyor's Michigan License No. 24624